

15-185-12793-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 1 Twp. 21 Rge. 12 ~~XX~~ (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE NE  
Lease Owner Imperial Petroleum Company, Inc.  
Lease Name FRANK COOK Well No. 3  
Office Address 903 Union Nat'l. Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed November 14 19 50  
Application for plugging filed April 18 19 51  
Application for plugging approved April 19 19 51  
Plugging commenced September 3 19 51  
Plugging completed September 8 19 51  
Reason for abandonment of well or producing formation  
Well turned to 100% water  
If a producing well is abandoned, date of last production March 19 51  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Arbuckle Depth to top 3427 Bottom 3471 Total Depth of Well 3471 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	280'	None
				5 1/2"	3428'	2133

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock from 3450' to 3420'. Dumped 5 sax of cement with dump bailer to 3420'. Top of cement 3385'. Filled hole with mud to 280', set rock bridge, dumped 15 sax of cement, top of cement 235'. Filled with mud to 35', dumped 10 sax for cap.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Imperial Petroleum Company, Inc.  
Address 903 Union Nat'l. Bank Bldg., Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of owner) ~~owner or operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL PETROLEUM COMPANY, INC.

(Signature) By: Raymond L. Bacon Sec.-Treas.

903 Union Nat'l. Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of September, 19 51



Margarette Intelle  
Notary Public.

My commission expires January 4, 1954  
23-3273-s 4-50-10M

PLUGGING  
FILE SEC LT 27 R 12  
BOOK PAGE 75 LINE 5

15-185-12793-00-00

WELL LOG

Imperial Petroleum Company  
Cock #3

NW SE NE  
Section 1 - T21-R12W

Stafford County, Kansas

Total Depth: 3430'  
Comm: 11-4-50. Comp: 11-14-50  
Contractor: Harms & Knight Drilling Co.  
Rotary: O-3430'.

Productions:  
Elevations:

Casing Records: 8 5/8" set @ 280' cemented w/200 sacks bulk cement - circulated.  
5 1/2" set @ 3428' cemented w/125 sacks cement.

Figures indicate bottom of formation:

Cellar	5		
Clay & shale	40		
Sand	165		
Shale & sand	225		
Shale & shells	240		
Red bed	280		
Shale	355		
Red bed	580		
Anhydrite	628		
Red bed	745		
Red bed & shale	1400		
Shale & lime	2740		
Lime	2805		
Shale & lime	2970		
Lime	3012		
Lime & shale	3205		
Lime	3430		
Total Depth	3430		
		<u>Tops</u>	
		Conglomerate	3403
		Simpson	3407
		Simpson shale	3411
		Arbuckle	3427
		Total Depth	3430

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

HARMS & KNIGHT DRILLING COMPANY

By JW Railback

Subscribed and sworn to before me this 29th day of November 1950.

Betty R. Rader  
Notary Public

My Commission Expires:

Aug 4, 1954

RECORDED  
INDEXED  
NOV 29 1950  
PAGE 75 OF 105