


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 9 Twp. 10 Rge. 21 (E) (W) x
Location as "NE/CNW/SW" or footage from lines C S/2 SW NE
Lease Owner Okmar Oil Co.
Lease Name Martin Webster Well No. #2
Office Address 1130 Vickers KBS&T Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 6-4-70 19
Application for plugging approved 19
Plugging commenced 6-26-70 19
Plugging completed 6-30-70 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well 3867' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3867'	444.87'
				8 5/8"	107'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3850'. Mixed and ran 5 sacks cement thru dump
bailer.
Squeezed hole with 3 sacks hulls, followed with 50 sacks cement, followed with 6 sacks
gel. Released plug and displaced with 70 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
7-2-1970
JUL 2 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of June, 19 70

My commission expires

Notary Public.



CERTIFIED DRILLERS LOG

Operator: W. L. Hartman Lease: Martin-Webster #2
 Contractor: H & H Drilling Company Location: CS/2 SW NE 9-10-21W
 Commenced: 3-30-51 Casing Record:
 Completed: 4-15-51 (With Rotary) 107' 8-5/8" cem. W/60 sax.
 3867' 5-1/2" cem. W/150 sax.
 Elevation: 2263 EDF
 Potential:

Formation	Depth	Remarks
Surface	0-107	
Shale	107-770	
Shale	770-1258	
Sand	1258-1405	
Shale	1405-1755	
Lime	1755-1810	
Shale	1810-1912	
Shale & Shell	1912-2256	
Shale & Lime	2256-2410	
Shale	2410-2618	
Shale & Lime	2618-3492	
Lime	3492-3662	
Chert & Lime	3662-3698	
Lime	3698-3726	
Lime & Shale	3726-3794	
Lime	3794-3822	
Chert & Lime	3822-3842	
Lime	3842-3852	
Arbuckle Lime	3852-3867	
Total Depth (Rotary)	3867	

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 5 1951
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log,
 to the best of my knowledge.

W. L. Hartman

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 11th day of May 1951.

Georgia L. Lard
 Notary Public

My Commission Expires: May 13, 1953