

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32047
Name: MICA Energy Corp
Address 1: P.O. Box 20707
Address 2: _____
City: Oklahoma City State: OK Zip: 73156 + _____
Contact Person: Michael E. Carr
Phone: (405) 942-4552
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Marmaton Depth to Top: 4357' Bottom: 4541' T.D. _____
LKC Depth to Top: 4203' Bottom: 4214' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 10120253 -00-00
Spot Description: _____
NW NE SE _____ Sec. 34 Twp. 16 S. R. 29 East West
1620 2310 Feet from North / South Line of Section
300 990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner: KCC PPT
 NE NW SE SW APS
County: Lane
Lease Name: Lohoff "A" Well #: 1
Date Well Completed: 10-20-1977
The plugging proposal was approved on: 7/21/2009 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 12-3-2009
Plugging Completed: 12-5-2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LKC, Marmaton	oil-water	Production	4 1/2"	4600'	-0-
Altamont, Pawnee	oil-water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP @4500'. Filled casing with sand to 4134'. Worked casing. Free point 807' +/- Pressured to 500 psi. Perforated @1300' with 3 JHPF. Cemented with 160 sacks 60/40 Pozmix with 4% gel. Cemented down 4 1/2" x 8 5/8" annulus with 200 sacks 60/40 Pozmix with 4% gel. SI with 25psi. Job complete 12-5-2009.

RECEIVED

Swift Services Inc. DEC 14 2009

Plugging Contractor License #: 31627 32382 Name: Fritzier Trucking, Inc.
Address 1: P.O. Box 544 Address 2: _____
City: Ness City State: KS Zip: 67560 + _____
Phone: (785) 798-3641

KCC WICHITA

Name of Party Responsible for Plugging Fees: MICA Energy Corp
State of Oklahoma County, Oklahoma, ss.
Michael E. Carr Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] 12-11-2009