


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 11 Twp. 10S Rge. 21 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines ~~XXXXXX~~ NE SE SW  
Lease Owner Peel-Hardman Oil Operators  
Lease Name Sutor "C" Well No. 1  
Office Address R. R. #3, Box 144B, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Nov. 21, 1956  
Application for plugging filed Nov. 21, 1956  
Application for plugging approved Nov. 21, 1956  
Plugging commenced Nov. 21, 1956  
Plugging completed Nov. 21, 1956  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3825 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	180	8 5/8"	180'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 3825' to 175' - heavy rotary mud and wooden plug  
175' to 129' - 15 sacks cement and 1/2 sack hulls  
129' to 40' - heavy rotary mud and wooden plug  
40' to 6' - 10 sacks cement and 1/2 sack hulls

**RECEIVED**  
STATE CORPORATION COMMISSION  
12-8-1956  
DEC - 8 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Peel Brothers, Inc.  
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Peel Brothers, Inc. (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. **PEEL BROTHERS, INC.**

(Signature) BY: Al H. Smith  
P.O. Box 88, Hoisington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1956

Ruch Brank  
Notary Public.

My commission expires April 27, 1960

**PLUGGING**  
FILE SEC 11 T 10 R 21W  
BOOK PAGE 120 LINE 39

DRILLERS' LOG

Company: Peel-Hardman Oil Operators  
Farm Name: Sutor "C" Well No. 1  
Total Depth: 3825'  
Comm: 11/14/56 Comp: 11/21/56  
Contractor: Peel Brothers, Inc.  
Casing: 8 5/8 @ 180' cem.

NE SE SW  
Sec. 11, Twp. 10S, Rge. 21W,  
County: Graham,  
Kansas  
Elevation:  
Production: Dry

Figures below indicate bottoms of formations:

Surface soils	0 -	180
Shale		820
Sand		950
Shale and shells		1070
Sand		1130
Red bed and shale		1710
Anhydrite		1740
Shale and lime		1970
Shale and shells		2300
Lime and shale		3505
Lime		3628
Lime and shale		3825
Total Depth		3825

This is to certify that the above information is to the best of our knowledge, true and correct.


PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 23rd day of November, 1956.

My commission expires: April 27, 1960

Ralph Brank  
Notary Public



FILED  
STATE CO.  
12-8-1956

PLUGGING  
FILE SEC 11 T 10 R 21W  
BOOK PAGE 120 LINE 39