


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham County, Sec. 10 Twp. 8S Rge. 23 (EX) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NE/4
Lease Owner Amerada Petroleum Corporation
Lease Name Irma Law Well No. 1
Office Address Box 197, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 7-17 19 55
Application for plugging filed 10-16 19 57
Application for plugging approved 10-17 19 57
Plugging commenced 12-1- 19 57
Plugging completed 12-3- 19 57
Reason for abandonment of well or producing formation Unprofitable to operate

If a producing well is abandoned, date of last production 10-14 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing K.C. Depth to top 3703' Bottom _____ Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	None
				5-1/2"	3948'	515'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3850'
Dumped 4 Sacks Cement 3850' to 3818'
Shot casing at 517', Pipe came free, pulled out 1 jt, mixing mud and circulating
Spot 20 Sacks Cement @ 500'
Pulled 260' 5-1/2" Casing
Spot 20 Sacks Cement @ 245'
Finished pulling 5-1/2" Casing. Total Recovered : 13 uts-515'
Spot 10 Sacks Cement in top of 8-5/8" Casing.

PLUGGING
FILE SEC. 8 T. 10 R. 23W
BOOK PAGE 54 LINE 8

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company
Address Box 221, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
R.A. Drake (employee of owner) ~~owner or operator~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.A. Drake

Box 197, Great Bend, Kansas
(Address)

5th day of December, 19 57



RECEIVED Charles W. Anderson

Notary Public.

DEC 6 1957

CONSERVATION DIVISION
Wichita, Kansas

ITMA LAW NO. 1

Section 8-106-23W
Graham County, Kansas
Amerada Petroleum Corporation

8-5/8" O. D. casing cemented at 245.49'
5-1/2" O. D. casing cemented at 3948'

Drilling commenced June 25, 1955
Drilling completed July 6, 1955

FROM	TO	FORMATION	REMARKS
0'	130'	Sand	
130	245	Shale & sand	
245	1230	Shale	8-5/8" O. D. casing cemented at 245.49'
1230	1295	Sand	
1295	1480	Shale, sand & red bed	
1480	1575	Sand & shale	
1575	1935	Shale	
1935	1990	Anhydrite	
1990	2285	Shale & shells	
2285	2450	Shale	
2450	2630	Shale & lime	
2630	2725	Lime	
2725	2780	Lime & shale	
2780	2835	Lime	
2835	2925	Lime & shale	
2925	3010	Shale	
3010	3190	Shale & lime	
3190	3360	Lime & shale	
3360	3420	Shale	
3420	3465	Sandy lime	
3465	3550	Shale & lime	
3550	3630	Lime & shale	
3630	3867	Lime	
3867	3875	Lime & chert	
3875	3950	Lime	5-1/2" O. D. casing cemented with 700 sacks of cement at 3948'
T.D.	3950'		

PLUGGING
 LE SEC 8 110 R234
 BOOK PAGE 54 8