


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 8 Twp. 10 Rge. 23 (W)

Location as "NE/CNW%SW%" or footage from line NW NW  
Lease Owner March Drilling Co., Box 463 Hutchinson, Kansas  
Lease Name Dietz Well No. 2  
Office Address P.O. Box 463, Hutchinson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) SWD well  
Date well completed 9-28-64 19  
Application for plugging filed November 12 19 66  
Application for plugging approved November 21, 1966 19  
Plugging commenced November 12, 1966 19  
Plugging completed November 12, 1966 19  
Reason for abandonment of well or producing formation  
No production on lease, there fore no use for SWD  
If a producing well is abandoned, date of last production none 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well W.L. Nichols, Morland, Kansas  
Producing formation none Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Pummed in cement first then 35 of jell  
Went back mixed 55 by hand and filled casing

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1966 12-30-66

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Company  
Address Duncan, Oklahoma


STATE OF Kansas COUNTY OF Reno, ss.  
A.J. Burke

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P.O. Box 463, Hutchinson, Kansas

(Address)

Subscribed and sworn to before me this 27 th day of December, 19 66



Holly Chappelle  
Notary Public.

15-065-19218-0000

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, KansasCompany- MARCH DRILG. CO.  
Farm- Dietz No. 2SEC. 8 T. 10 R. 23W  
NW NW NWCounty Graham  
KANSASTotal Depth. 4025'  
Comm. 9-12-64 Comp. 9-23-64  
Shot or Treated.  
Contractor. Co. Tools  
Issued. 1-2-65

## CASING:

8 5/8" 182' w/140' sx cem.  
5 1/2" 2040' w/150' sx cem.

Elevation. 2431' R.B.

Production. Input well.

Figures indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE.

Rare trace of light brown oil stain in white crystalline limestone. No odor &amp; no free oil in wet samples. Saturation spotted. Low porosity. This zone is of no commercial value.

3787-3789'

DST # 2 - 3942' - 3997' Op. 1 hr.  
Blow weak throughout test. Rec. 55' of drilling mud. IBHP 313#/1 hr. IFP 32#; FFP 43#; FBHP 194#/1 hr.

Ran Great Guns log.

Very rare tr. of spotted light brown oil stain in buff oolitic limestone. No odor &amp; no free oil in wet samples. This zone is of no commercial value.

3827-3829'

Rare tr. of brown oil stain in buff crystalline to matted oolitic limestone. No odor &amp; no free oil in wet samples. Traces of pinpoint porosity. This zone is of no commercial value.

3861-3883'

Scattered light brown oil stain in buff crystalline &amp; oolitic limestone. Saturation fair. No odor and no free oil in wet samples. Traces of pinpoint. This zone covered by drill stem test #1. This zone is of no commercial value.

3942-3945'

Trace of light brown oil stain in buff crystalline limestone. No odor and no free oil in wet samples. Low order porosity. Saturation spotted. This zone covered by drill stem test #2. This zone is of no commercial value.

3959-3962'

Occasional light brown oil stain in buff crystalline. No odor and no free oil in wet samples. Saturation spotted. Traces of pinpoint porosity. This zone covered by drill stem test #2. This zone is of no commercial value.

3978-3982'

TOTAL DEPTH

4025

## TOPS:

*Cheyenne (Sc)	3715
Hydrite	2035
Topeka	3530
Heebner	3738
Toronto	3770
Lansing Kansas City	3786

DST # 1 - 3930'-3952' Op. 1 hr..  
Blow, weak flow for 10 min. Rec.  
20' drilling mud. IBHP 32#/1 hr.  
IFP 15#; FF) 23#; FBHP 28#/1 hr.RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas