

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Griffith

WELL NUMBER 1
_____ Ft. from S Section Lin

NE NW NW _____ Ft. from E Section Lin

SEC. 2 TWP. 10 RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 9/51

Plugging Commenced 1-9-96

Plugging Completed 1-9-96

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

The plugging proposal was approved on 1-9-96 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4098 PBDT

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	245	8 5/8		
	Casing	0	4142	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other products were used, state the character of same and depth placed, from _____ feet to _____ feet each

Big up Mercury run free point. Stacked out at 3708'. Free at 3705'. Back off at 3600'. 3692'
Mix 100 sk. 60/40 pos 10% gel 500# hulls 2211' mix 100 sk. 60/40 pos 10% gel 150# hulls
762' mix 55 sk. 60/40 pos, 10% gel 200# hulls. Circulate to surface. Hook to 5 1/2. Mix 25
sk. 60/40 pos, 10% gel Max pressure 500#. Shut in 500# Hook to 8 5/8 mix 85 sk. 60/40
pos, 10% gel, 150# hulls. Max. pressure 650#. Shut in 250#.

Name of Plugging Contractor Berexco, Inc. License # 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc. JAN 19 1996

STATE OF Kansas COUNTY OF Ellis


Mr. Ted Crawford (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed
the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks. 67601

16 day of January, 19 96

Rosemary Smith Notary Public



My Commission Expires: 5-1-1999

USE ONLY ONE SIDE OF EACH FORM