

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Griffith  
WELL NUMBER 4  
         Ft. from S Section Lin  
S $\frac{1}{4}$  NW NW Ft. from E Section Lin  
SEC. 2 TWP. 10 RGE. 23 (E) or (W)  
COUNTY Graham  
Date Well Completed 11/53  
Plugging Commenced 12/29/95  
Plugging Completed 12/29/95

LEASE OPERATOR Berexco, Inc.  
ADDRESS Box 723 Hays, Kansas 67601  
PHONE#(913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/29/95 (date)  
by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4170 PBTB  
Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1996

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	262	8 5/8		
	Casing	0	4220	5 $\frac{1}{2}$		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from          feet to          feet each side of casing.  
Run tbg. opened to 3697'. Mix 15 sk. gel. Max. 60/40 pos. 10% gel with 500# hulls. Pull tbg. to 1991'. Mix 75 sk. 60/40 pos. 10% gel with 150# hulls. Pull tbg. to 976'. Mix 80 sk. 60/40 pos. 10% gel with 200# hulls. Circ. to surface. Hook to 5 $\frac{1}{2}$  Mix 15 sk. 60/40 pos 10% gel. Max. press. 800#. Shut in 700#. Hook to 8 5/8. Mix 50 sk. 60/40 pos, 10% gel. Max. press. 100#. Shut in 0#.

Name of Plugging Contractor Berexco, Inc. License No. 5363


Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed with the Commission and the same are true and correct, so help me God.

(Signature) Ted Crawford  
(Address) Box 723 Hays, KS 67601  
before me this 10 day of January, 1996  
Rosemary Smith  
Notary Public



My Commission Expires: 5-1-1999  
USE ONLY ONE SIDE OF EACH FORM