

15-065-00177-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 2 Twp. 10 Rge. (E) 23(W)

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Harry Gore
Lease Name Frank Law Well No. 1
Office Address 400 Brown Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed July 1, 1951 19
Application for plugging filed Sept. 22, 1953 19
Application for plugging approved Sept. 22, 1953 19
Plugging commenced Sept. 28, 1953 19
Plugging completed Oct. 17, 1953 19
Reason for abandonment of well or producing formation oil exhausted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production July 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4270 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	178'	cemented
				5 1/2	4201'	1114'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4164 to 4100'	sand bridge
4100 to 4080'	4 sks. cement
4080 to 175'	mudded
175 to 165'	rock bridge
165 to 135'	15 sks. cement
135 to 30'	mud
30 to cellar	10 sks. cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1953 10-28-53
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & S Pipe Pulling Co.
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Ralph Gore (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Gore Partner
400 Brown Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 19 53
Charlotte Klitchka
Notary Public.



PLUGGING
FILE SEC 2 T 10 R 23W
BOOK PAGE 130 LINE 40

COMPANY: HARRY GORE

NE-NE-SW, Sec. 2,
Twp. 10-Rge, 23 W,
Graham County, Kansas.

LEASE: Frank Law #1

Elevation: 2437 Derrick Floor

Note: All meas. rotary bushings.

0	45 Sand & shale
45	140 Blue shale
140	178 shale
178	600 shale
600	950 Shale
950	1080 sand, shale
1080	1290 Shale, shells
1290	1525 Shale
1525	1555 Sand
1555	1600 Sand & shale
1600	1910 Shale & shells
1910	2005 Shale & shells
2005	2055 Anhydrite
2055	2175 Shale
2175	2355 Shale & shells
2355	2495 Shale & lime
2495	2595 Shale & lime
2595	2695 Lime & shale
2695	2805 Shale & lime
2805	2870 Lime & shale
2870	2920 Lime
2920	3000 Lime & shale
3000	3050 Shale & lime
3050	3035 Shale & lime
3035	3200 Shale & lime
3200	3245 Lime & shale
3245	3285 Lime & shale
3285	3330 Shale & lime
3330	3440 Shale & lime
3440	3490 Lime
3490	3550 Lime & shale
3550	3595 Lime, shale
3595	3655 Lime & shale
3655	3700 Lime & shale
3700	3730 Lime
3730	3780 Lime
3780	3795 Lime
3795	3815 Lime
3815	3860 Lime
3860	3905 Lime
3905	3928 Lime
3928	3935 Lime
3935	3980 Lime
3980	4020 Shale
4020	4065 Lime
4065	4090 Lime
4090	4125 Shale
4125	4141 Lime & Sand
4141	4155 Lime & Sand
4155	4190 Conglomerate
4190	4210 Lime & shale & Chirt
4210	4240 Chirt
4240	4260 Conglomerate
4260	4270 Arbuckle
4270	T.D. rotary bushing meas.)

TOPS

Anhydrite	2005	Base K.C.	3953
Topeka	3477	Marmaton	
Heebner	3689	Congl.	4046
Dodge Lime	3710	Sand	4124-38
Lans. K.C.	3720	Cherty Congl	4149
Arbuckle	4253		
T.D.	4270		

D.S.T. by Sun Cementing Co.

3789'-3815' Tool open 1 hour
recovered 540' slightly oil &
gas cut muddy salt water. B.H.P.
15 min-1150#. Flowing Press. 150#

D.S.T. By Johnston Testing Co.

3902'-3928' Tool open 1 hour.
recovered 10' Oiley, Mud. B.H.P.
15 min-0. Flowing press-0.

D.S.T. by Sun Cementing Co.

4126'-4140' Tool open 1 hour
Recovered 240' of very slightly
mud cut oil. Slow study blow.
B.H.P. 15 min. 1000#

CASING RECORD:

8 5/8" Surface casing set at
178' w/150 sks Cement by
Globe Cementing Company.

5 1/2" production string set at
4201' (Rotary bushing correction
R.B. to Braden Head 7 feet).
w/175 Sacks cement by Halliburton.

Ran Schlumberger to Total Depth.

COMMENCED: 6-13-51
COMPLETED: 7-1-51

PLUGGING

FILE SEC 2-T-10-R-234
BOOK PAGE 130 LINE 40

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Frank Law #1, located NE-NE-SW, Section 2, Twp. 10, Rge. 23W, Graham County, Kansas.

CONTRACTOR: STRAIN DRILLING CO.

By T.C. Strain

Subscribed and sworn to before me this 5th day of July, 1951
My Commission expires 6-19, 1955.

Clouis K Emrich
Notary Public.