

15-195-20403-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Trego County. Sec. 4 Twp. 12S Rge. 22W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW/4 SE/4 SW/4

Lease Owner Little George Oil Company
Lease Name Hillman Well No. 1


Office Address 4th Financial Center, Suite 680, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) _____
D & A

Date Well completed April 3, 1977
Application for plugging filed April 3, 1977
Application for plugging approved April 3, 1977
Plugging commenced April 3, 1977
Plugging completed April 4, 1977
Reason for abandonment of well or producing formation _____
D & A

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4127'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1977
04-13-1977
CONSERVATION DIVISION
Wichita, Kansas

Plugged hole @ 850' w/70 sx 50-50+ Pozmix, 6% Gel
Plug @ 250' w/20 sx cement
Bridge @ 40' w/10 sx cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB&T Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss. contractor
Gloria Fawcett (employee of ~~owner~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of April, 1977.

Joyce A. Hagermann
Notary Public.

My commission expires _____



15-195-20403-00-00

DRILLERS LOG

No. 1 Hillman

CASING RECORD:

COMPANY: Little George Oil Company

DESCRIPTION:

8 5/8" @ 254'
w/175 sx cement

CONTRACTOR: Red Tiger Drilling Company

NW/4 SE/4 SW/4
Sec. 4-T12S-R22W
Trego County, Kansas

COMMENCED: March 25, 1977

COMPLETED: April 4, 1977

TOTAL DEPTH: 4,127'

ELEVATION: 2,400' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	259	
Clay & Shale	259	975	
Shale, Shells, & Sand	975	1170	
Blaine Anhydrite	1170	1183	
Shale	1183	1624	
Red Bed	1624	1675	
Shale & Red Bed	1675	1839	
Anhydrite	1839	1881	
Shale	1881	2260	
Shale & Lime Streaks	2260	2475	
Shale	2475	2560	
Lime	2560	3035	
Lime & Shale	3035	3170	
Lime	3170	4127	
RTD		4127	

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1977
04-13-1977
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 11th day of April, 1977.

Joyce A. Hagermann
Notary Public

