


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-195-00369-00-00 (3)

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Trego County. Sec. 3 Twp. 12 Rge. 22W (E) (W)  
Location as "NE/CNWxSWx" or footage from lines SE SE NW  
Lease Owner K & E Drilling, Inc.  
Lease Name Riggs Well No. 1  
Office Address 719 Union Center Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 6-19-58 19  
Application for plugging filed 6-19-58 19  
Application for plugging approved 6-19-58 19  
Plugging commenced 6-19-58 19  
Plugging completed 6-19-58 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	223'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 600', set plug with 20 sx cement through drill pipe. Filled with heavy mud to 210', set plug with 20 sx cement. Filled with heavy mud to 40', set solid bridge with 1/2 sack hulls and 10 sx cement to base of cellar. Job complete.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 2 1958  
07-02-1958  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Clinton Engstrand (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clinton Engstrand, K & E Drilling, Inc.  
719 Union Center Bldg. Wichita, Kansas (Address)

Subscribed and sworn to before me this 20th day of June, 1958

My commission expires March 26, 1959

Helen Y. Langston Notary Public.

PLUGGING  
FILE SEC 3 T 12 R 22W  
BOOK PAGE 109 LINE 31

15-195 00369-00-00

DRILLER'S LOG

OPERATOR: K & E DRILLING, INC.  
719 Union Center  
Wichita 2, Kansas

FARM: #1 RIGGS  
LOCATION: SE SE NW  
Sec. 3-12S-22W  
Trego County, Kansas

CONTRACTOR: K & E DRILLING, INC.  
719 Union Center  
Wichita 2, Kansas

COMMENCED: June 10th, 1958  
COMPLETED: June 19th, 1958

CASING: 8-5/8" @ 223' (160 sx)

ELEVATION: 2387' KB  
PRODUCTION: D & A

R.T.D. 4128'

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Top Soil & Clay	45
Sand	55
Shale & Shells	750
Shale & Sand	1280
Sand	1530
Shale & Red Bed	1835
Anhydrite	1870
Shale & Shells	2190
Shale & Lime	2430
Lime	2725
Lime & Shale	3070
Lime	3970
Lime & Shale	4128
R.T.D.	4128


CERTIFICATION

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

I, Dale Silcott of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the #1 RIGGS well.

  
Dale Silcott

Subscribed and sworn to before me this 30th day of June, 1958.

  
Patricia M. Edwards, Notary Public

My commission expires: August 11th, 1958.

STATE OF KANSAS  
JUL 2 1958  
07-2-1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 3 T. 12 R. 22W  
BOOK PAGE 109 LINE 31