

15-005-01819-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER None  
LEASE NAME Schneider A  
WELL NUMBER 4  
1980 Ft. from S Section Line  
4950 Ft. from E Section Line  
SEC. 36 TWP. 10S RGE. 21 (E) or (W)  
COUNTY Graham  
Date Well Completed 10/8/54  
Plugging Commenced 8/31/93  
Plugging Completed 9/2/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filled? On old form If not, is well log attached? -

Producing Formation Lansing/Arbuckle Depth to Top 3532 Bottom 3694 T.D. 3694

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	Oil	3532	96	8 5/8	207	-0-
Arbuckle	Oil	3664	94	5 1/2	3664	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
RU. Tried to pull tbg OOH. Tbg. stuck - cut off @ 2500'. Perf'd 5 1/2" casing @ 2120' & pumped 50 sxs to 1690'. Tied onto 8 5/8" & pumped 50 sxs 65/35 poz w/10% gel down annulus. Pulled up hole to 1350' and circ'd cmt to surf w/150 sxs + 300# hulls. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.


Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 04 1993  
CONSERVATION DIVISION  
Wichita, Kansas



SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 93

Lud Mundock  
Notary Public

My Commission Expires: 12-23-97

15-065-01819-0000  
R

G. H. D. Kaiser  
909 Polansky Bldg.


KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLING BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK WICHITA, KANSAS

COMPANY Herman Geo. Kaiser  
FARM " " " " NO. 4  
Schneider A

SEC. 36 T. 10S R. 21W  
LOC. C W/2 NW SW

TOTAL DEPTH 3666'  
COMM. 9/27/54 COMP. 10/8/54  
SHOT OR TREATED  
CONTRACTOR H-30, Inc.  
ISSUED

COUNTY Graham  
KANSAS



CASING

20	10
15	8 207'
12	6
13	5 3664'

ELEVATION 2101 K.B.  
PRODUCTION 406 Bbls/Dw

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Find Sand	70
Sand & Course Gravel	125.
Shale	850
Shale & Shells	1020
Sand	1300
Shale, Shells & Red Bed	1320
Shale & Red Bed	1547
Anhydrite	1600
Red Bed & Shale	1785
Shale, Shells & Red Bed	2045
Shale, Shells & Salt	2140
Shale & Lime	3393
Lime & Shale - Broken	3450
Lime & Shale	3550
Lime	3598
Lime & Shale	3663
Lime	3666

*2101*  
*16*  
*501*

FORMATION TOPS (K.B. Meas.)

HEEBNER	3329
TORONTO	3350
LANSING	3369
BASE KANSAS CITY	3601
CONGLOMERATE	3640
SIMPSON DOLOMITE	3660
ARBUCKLE	3663

*2101*  
*1547*  
*554*

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *H. P. Spangenberg*

STATE OF KANSAS  
COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 11th day of October, 1954.

*Rose Lury*  
Notary Public

My Commission expires February 13, 1956.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1993  
CONSERVATION DIVISION  
Wichita, Kansas