

15-065-01822-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Schneider A

WELL NUMBER 7

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 10S RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 1/29/55

Plugging Commenced 9/2/93

Plugging Completed 9/2/93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? On old form If not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3648 Bottom 3666 T.D. 3666

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3648	66	8 5/8	200	-0-
				7	3648	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU & perf'd 7" casing @ 2120' (2 SPF). Pumped 150 sxs 65/35 poz w/10% gel. Pulled up hole to 1300' & circ'd cmt to surface w/190 sxs cmt + 400# hulls. Tied onto 8 5/8" but could not pump into @ 500#. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License STATE CORPORATION COMMISSION

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 93

Lud M. Mardock
Notary Public

My Commission Expires: 12-23-93

RECEIVED
STATE CORPORATION COMMISSION
OCT 04 1993
CONSERVATION DIVISION
Wichita, Kansas

COMPANY Herman Geo. Kaiser, Oil Producer

SEC. 36 T. 10 R. 21W

FARM Schneider A NO. 7

LOC. SW SE SW

TOTAL DEPTH 3654

COUNTY Graham

COMM. 1/16/55


COMP. 1/29/55

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20	10
15	8 199'
12	6 3648'
13	5

ELEVATION 2086 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Sand	45
Sand & Shale	75
Shale with sand streaks	110
Shale	200
Shale & Shells - strks. sand	940
Sand, shale & Red Bed	1060
Sand	1280
Shale & Red Bed with strks. sand	1295
Shale & Red Bed	1535
Shale, Shells & Red Bed	1540
Anhydrite	1590
Shale & Shells	2160
Shale, Lime & Salt	2245
Shale & Lime	3377
Lime	3470
Lime & Shale	3538
Lime	3575
Lime & Shale	3626
Conglomerate	3646
Arbuckle	3654

2086
 1540

 4546

FORMATION TOPS

HEEBNER	3317
TORONTO	3340
LANSING	3356
BASE KANSAS CITY	3583
SHALEY CONGLOMERATE	3625
CHERTY CONGLOMERATE	3632
ARBUCKLE	3646

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

By R. P. Sproull
 Notary Public, Kansas

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 3rd day of February, 1955.

RECEIVED
 STATE CORPORATION COMMISSION
Rose L. Sproull
 Notary Public

JUL 19 1993

My Commission expires February 13, 1956.

CONSERVATION DIVISION
 Wichita, Kansas