

15-065-01820-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Schneider A

WELL NUMBER 5

990 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 36 TWP. 10 SRGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 10/20/54

Plugging Commenced 8/31/93

Plugging Completed 9/2/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? On old form If not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3668 Bottom 3677 T.D. 3677

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3668	77	8 5/8	204	-0-
				5 1/2	3668	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU. Tried to pull tbg OOH. Tbg stuck - cut off @ 2500'. Perf'd 5 1/2" casing to 2120' & spotted 50 sxs cmt to 1700'. Tied onto 8 5/8" & pumped 50 sxs 65/35 poz w/10% gel down annulus. Pulled up hole to 1330' & circ'd to surf w/250 sxs cmt + 100# hulls. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) C. Van Valkenburg  
(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 93

Linda M. Munk  
Notary Public

My Commission Expires: 12-23-93

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 04 1993  
CONSERVATION DIVISION  
Wichita, Kansas




WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-065-01820-0000  
SEC. 36 T. 10 R. 21W  
NE SW SW

Company- HERMAN GEO. KAISER  
Farm- Schneider "A" No. 5

Total Depth. 3674  
Comm. 10-9-54 Comp. 10-20-54  
Shot or Treated.  
Contractor. H-30, Inc.  
Issued. 1-8-55

County Graham  
KANSAS



Elevation. 2092 KB.

Production. 176 bbls.

CASING:

8 5/8 204'  
5 1/2 3668'

Figures indicate Bottom of Formations.

surface clay	40
surface clay & sand	130
shale & gravel	153
shale	1010
sand	1320
shale & red bed	1543
anhydrite	1585
shale, shells & red bed	1900
shale & lime	2100
shale, lime & salt	2220
shale & lime	3305
lime & shale streaks	3357
lime	3398
lime & shale	3435
lime & shale streaks	3488
lime & shale	3570
lime	3603
lime & shale	3660
lime & chert	3674
Total Depth	

TOPS: (KB Meas.)

Heebner	3327
Toronto	3349
Lansing	3368
Base KC	3600
Conglomerate shale	3636
Cherty conglomerate	3647
Arbuckle	3667

RECEIVED  
STATE CORPORATION COMMISSION

JUL 19 1993

CONSERVATION DIVISION  
Wichita, Kansas