

15-065-01821-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Schneider A

WELL NUMBER 6

330 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 36 TWP. 10S RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 11/17/54

Plugging Commenced 8/31/93

Plugging Completed 9/1/93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? On old form If not, Is well log attached? -

Producing Formation Lansing/Arbuckle Depth to Top 3394 Bottom 3653 T.D. 3653

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil	3394	97	8 5/8	208	-0-
Arbuckle	Oil	3647	53	5 1/2	3647	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. POOH w/tbg & rods. Perf'd 5 1/2" casing @ 2120'. Tied onto 8 5/8" & pumped 50 sxs 65/35 poz w/10% gel down annulus. Tied onto 5 1/2" casing & pumped 300 sxs 65/35 poz w/10% gel + 500# hulls to surf. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 06390

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or Conservation Division

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg


(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 30th day of September, 1993

Ludi Mandork
Notary Public

My Commission Expires: 12-27-93

6568
06390
RECEIVED
STATE CORPORATION COMMISSION
OCT 04 1993
CONSERVATION DIVISION
Wichita, Kansas



15-065-01821-0000


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser
 FARM Schneider A NO. 6

SEC. 36 T. 10S R. 21W
 LOC. SE SW SW

TOTAL DEPTH 3653
 COMM. 11/4/54 COMP. 11/17/54
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Graham
 KANSAS



CASING
 20 10
 15 8 208'
 12 6
 13 5 3647'

ELEVATION 2090 K.B.
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface	Clan, Sand & Shale	190
Shale		630
Shale & Red Bed		700
Shale		1025
Sand		1230
Shale, Shells & Red Bed		1500
Red Bed & Shale		1515
Anhydrite		1590
Shale & Shells		2040
Shale & Lime		3365
Lime		3386
Shale & Lime		3465
Lime		3496
Shale & Lime		3507
Lime		3653

2090
 1515

 1575

FORMATION TOPS (K.B. Meas.)

HEEBNER	3315
TORONTO	3338
LANSING-KANSAS CITY	3354
BASE KANSAS CITY	3629
ARBUCKLE	3646

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *[Signature]*

STATE OF KANSAS
 COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 22nd day of November, 1954.

[Signature]
 Notary Public

My Commission expires February 13, 1956.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 19 1993
 CONSERVATION DIVISION
 Wichita, Kansas