

15-065-01826-0000

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S Market, Room 2078
Wichita, KS 67202

API NUMBER 15-065-1958
LEASE NAME Trico West Unit
WELL NUMBER #111

TYPE OR PRINT
NOTICE: Fill out completely and return 3630' ft. from S Section Line
to Cons. Div. office within 30 days. 330' ft. from E Section Line

LEASE OPERATOR OXY USA INC.
ADDRESS P.O. Box D, Plainville, KS 67663
PHONE # 785-434-7681 OPERATOR'S LICENSE NO. 5447
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply)

Spot Location _____
SEC 36 TWP 10 S RGE 21 or (TW)
COUNTY Graham
Date Well Completed 4-7-58
Plugging Commenced 9-30-97
Plugging Completed 9-30-97

The plugging proposal was approved on December 4, 1996 (date)
by David Williams (KCC District Agent's Name)

Is ACO-1 filed? ON FILE If not, is well log attached? _____

Producing Formation Arbuckel Depth to Top 3553' Bottom 3600' T.D. 3727'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
		5'	240'	8-5/8"	240'	0'
		0'	3717'	5-1/2"	3717'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

*** See back for details ***

RECEIVED

STATE CORPORATION COMMISSION

JAN 27 1998

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co.
Address Russell, KS
License No: NA

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF Kansas COUNTY OF Rooks, ss.
J.D. Hininger

(Employee of Operator) or (Operator) of above-described well, being first duly sworn

on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.D. Hininger
(Address) P.O. Box D, Plainville, KS 67663

SUBSCRIBED AND SWORN TO before me this 26th day of January, 1998

Sheryl Axelson Notary Public

My Commission Expires:
5-20-2000



10/01/97 JOB: Plug and Abandon; CMIC: JD Hininger

P&A - Rigged up and ran 2" tbg. open ended to 3600 ft. - Tried to pump into 8 5/8" - pressured up to 300 psi - 5 1/2" - Mixed and pumped 100 sks of gel and 125 sks 60/40 cement w/10% gel w/300 lbs. hulls (Note) the gel will be spotted from 1600 ft. up to 1200 ft. - Pulled tbg. to 1200' - Mixed and pumped 100 sks. w/200 lbs. hulls and circulated cement to surface - Pulled tbg. - Finished filling 5 1/2" to surface w/10 sks. - Plugged @ 12:00 noon 09/30/97 - Under the direction of Dennis Hamel

L/E \$ 2333; MAT \$ 2339; CUM: L/E \$ 2333, MAT \$ 2339, TOT \$ 4672;

15-065-01826-0000

111

RECEIVED
STATE CORPORATE COMMISSION

JAN 27 1998

GENERAL DIVISION