


15-065-00543-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 14 Twp. 10S Rge. 22W (X) (W)

Location as "NE/CNW/SW" or footage from lines SW 1/4 SW 1/4 SW 1/4

Lease Owner Houston, Chandler & Simpson Oil Co. & Leben Drilling Inc.

Lease Name Faulkner Well No. 1

Office Address 905 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-17-58 19

Application for plugging filed 11-17-58 19

Application for plugging approved 11-17-58 19

Plugging commenced 11-17-58 19

Plugging completed 11-17-58 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation Depth to top Bottom Total Depth of Well 3885' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	228'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 600' w/20 sacks cement
2nd plug @ 225' w/20 sacks cement
top plug @ 40' w/10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 - 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Frank Hamlin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 58

My commission expires June 17, 1961

Ruth N. Benjamin
Notary Public.

PLUGGING
FILE SEC 14 T 10 R 22W
BOOK PAGE 1 LINE 8

DRILLER'S LOG

COMPANY: HOUSTON, CHANDLER & SIMPSON OIL CO. &
 LEHEN DRILLING, INC.
 CONTRACTOR: LEHEN DRILLING, INC.
 FARM: FAULKNER #1
 LOCATION: SW $\frac{1}{2}$ SW $\frac{1}{2}$ SW $\frac{1}{2}$ SEC. 14-10S-22W
 GRAHAM COUNTY, KANSAS
 COMMENCED: 11-6-58
 COMPLETED: 11-17-58

0	825	Shale & Shells
825	950	Sand & Shale
950	1050	Shale, Sand & Shells
1050	1350	Shale
1350	1415	Sand
1415	1475	Shale
1475	1721	Shale, Shells & Redbed
1721	1760	Anhydrite
1760	2000	Shale & Shells
2000	2210	Shale
2210	2570	Shale & Lime
2570	2695	Lime
2695	3330	Shale & Lime
3330	3395	Shale
3395	3455	Shale & Lime
3455	3495	Shale
3495	3810	Lime
3810	3830	Chert
3830	3885	Lime
	<u>3885</u>	<u>Rotary Total Depth - D & A</u>

Caslock

Set 8 5/8" surface casing @ 225' with 100 sacks cement & 2% CaCl.

Fidelity Union Bank

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the Faulkner #1, located SW $\frac{1}{2}$ SW $\frac{1}{2}$ SW $\frac{1}{2}$ Section 14, Township 10 South, Range 22 West, Graham County, Kansas, as reflected by the files of Lehen Drilling, Inc.

LEHEN DRILLING, INC.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 20th day of November, 1958.

Ruth H. Benjamin
Ruth H. Benjamin - Notary Public

My commission expires:
June 17, 1961



RECEIVED
CORPORATION COMMISSION
NOV 23 - 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 14 T. 10 R. 22W
BOOK PAGE 1 LINES