

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-20,897-0000

LEASE NAME Holmquist-Holmes

WELL NUMBER #3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 14 TWP. 10 RGE. 22W (E) or (W)

COUNTY Graham

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, KS

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed 3-77

Character of Well Oil

Plugging Commenced 9-29-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-29-93

The plugging proposal was approved on 9-29-93 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation L/KC Depth to Top 3500 Bottom 3683 T.D. 3760

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	131	-0-
				4 1/2"	3752	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 50 sxs 60/40 poz 10% gel & 100# hulls down tbq with no circulation. Pulled tbq to 1540' & pumped 80 sacks & 100# hulls down tbq. Cmt circ to surface. Pulled remainder of tbq & pumped 70 sacks down 4 1/2" csg. Max pressure 400#, SIP 300#. Pumped 75 sxs down 8 5/8", max press 100#, SIP 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1993

Lisa Thimmesch
Notary Public

My Commission Expires:

