

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-21037-00-00
API NUMBER ~~15-065-21,127-0000~~

LEASE NAME Holmquist-Holmes

WELL NUMBER 5

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 14 TWP. 10 RGE 22W (E) or (W)

COUNTY Graham

Date Well Completed 7-78

Plugging Commenced 6-7-93

Plugging Completed 6-8-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, KS

PHONE# (316)-267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 27, 1993 (date)

by Dennis Hamel (KCC District Agent's Name).

Is AC0-1 filed? yes If not, is well log attached? _____

Producing Formation L/KC Depth to Top 3713' Bottom 3675' T.D. 3797'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	204	-0-
				4 1/2	3785	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Shot at 2500'. Ran tubing to 2500'. Spotted cement to surface. Squeezed 4 1/2" with total of 215 sxs with cement at surface. Squeeze 8 5/8" with 60 sxs to max pressure 450#. Close in PST 150#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service License No. _____

Address Victoria, Kansas 67671

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 29th day of June RECEIVED 93

STATE CORPORATION COMMISSION

Notary Public

My Commission Expires:



JUN 30 1993