

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-21,904-000

LEASE NAME Tremblay

WELL NUMBER 2

SPOT LOCATION C.E/2 SE NE

SEC. 14 TWP. 10 RGE. 22 ~~W~~ (W)

COUNTY Graham

Date Well Completed 2-4-1984

Plugging Commenced 8-14-1984

Plugging Completed 8-14-1984

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Calvin Noah

ADDRESS 329 N. Birch, Valley Center, Ks 67147

PHONE # (316) 755-1032 OPERATORS LICENSE NO. 5616

Character of Well OIL  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? DIST. # 6, 1014 Cody, Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached?

Producing formation Marm-Lans KC. Depth to top perf 3562 bottom Perf. T.D. 3930  
3868

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Marmaton	Oil	3856	3868	8 5/8"	253.16'	None
Lans-KC	Oil	3754	3761	4 1/2"	3929'	None
"	Oil & Water	3599	3601			
"	Oil & Water	3562	3564			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Perf. 4 shots at 1788-1789 (Top of Anhydrite). Cemented down 4 1/2 casing at 500 # Max Press. Pumped 2 sax Gel mixed with 2 sax hulls, then 50 sax 50/50 Posmix, 6 % Gel, 3 % CC, then pumped 11 sax Gel, Then 100 sax 50/50 posmix cement and shut in. Pumped down annulus at 150 # Max Press: mixed 4 sax gel then 50 sax 50/50 posmix, 6% gel, 3 % CC & shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pfeifer Well Service, Inc. License No. 6967  
Address P. O. Box 386, Hill City, Kansas 67642

STATE OF Kansas COUNTY OF Graham, ss.

RECEIVED  
STATE CORPORATION COMMISSION

Bill Daily (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

OCT 15 1984

(Signature) Bill Daily

(Address) Box 386, Hill City, Ks. 67642

CONSERVATION DIVISION  
Wichita, Kansas

Debra L. Pfeifer-Wente  
NOTARY PUBLIC  
State of Kansas  
My Appointment Expires:

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1984

Debra L Pfeifer-Wente  
Notary Public

My Commission expires: May 12, 1986