

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,127-0000

LEASE NAME Holmquist-Holmes

WELL NUMBER 6

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from S Section Line

1040 Ft. from E Section Line
NW/4

SEC. 14 TWP. 10 RGE. 22W(E) or (W)

COUNTY Graham

Date Well Completed 6-79

Plugging Commenced 6-2-93

Plugging Completed 6-7-93

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-20-93 (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Lansing Depth to Top 3541' Bottom 3684 T.D. 3820

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	208	-0-
				4 1/2	3819	1003'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand back to 3490' w/4 sxs common w/bailer. Shot at 2300' and 1800'. Mix & pump 75 sxs cement blend. Displace to 1050'. Shot recovered 1025'. Lay down rack & skid. Pump 60 sxs cement blend. Lay down to 300'. Circulate cement to surface with total 250 sxs cement blend.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 20th day of June 1993

RECEIVED 93
STATE CORPORATION COMMISSION

My Commission Expires:

LISA THIMMESCH
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 3-27-95

Notary Public JUN 30 1995

CONSERVATION DIVISION
Wichita, Kansas
Rev. 1-88 CP-4
05-88