

15-065-20940-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas, 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER spud 8/3/77

LEASE NAME Holmquist-Holmes

WELL NUMBER 4
4950

330 Ft. from S Section Line

3630 Ft. from E Section Line
990 *ETCC*

SEC. 14 TWP. 10 RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 9/24/99

Plugging Completed 9/24/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1999
11-29-99
CONSERVATION DIVISION

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188, Wichita, KS 67278-3188

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/24/99 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? sent with CP-1

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	oil & brine			8 5/8		-0-
				4 1/2		-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Perforated 4 1/2" casing at 1800' (Anhdrite) and 970' (Dakota). Ran 2" tubing to 1845'. Pumped 100 sacks 60/40 pozmix and 10% gel and 400# shulls down 4 1/2" casing. Pulled tbq up to 1032'. Pumped 65 sacks 60/40 pozmix, 10% gel, 100# hulls down 4 1/2" casing. Cement circulated to surface. Pulled tubing out of hole. (over)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. not required

Address P.O. Box 31, Russell, KS 67765

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

David F. Jamis (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David F. Jamis

(Address) P.O. Box 783188, Wic., KS 67278

A. ANDREA PEREZ
Notary Public - State of Kansas
My Appt. Expires 01/26/2002

SUBSCRIBED AND SWORN TO before me this 24th day of November, 1999

My Commission Expires: January 26, 2002 Notary Public Andrea Perez

PP. PK-11

Loaded and squeezed 4 1/2" casing with 40 sacks 60/40 pozmix, 10% gel. Max psi = 200#. Shutin at 200#. Pumped 50 sacks 60/40 pozmix, 10% gel and 100# hulls down 8 5/8ths" casing. Max PSI = 600#. Shutin at 300#. Plugging complete at 12:45 pm, 11/24/99. Witnessed and approved by Dennis Hamel with the Kansas Corporation Commission.