

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-20,757-0000

LEASE NAME Holmquist-Holmes

WELL NUMBER #1

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 14 TWP. 10 RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 11/26/91

Plugging Completed 11/26/91

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 26, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Lansing/KC Depth to Top Perf @ 3496' Bottom Perf @ 3682' T.D. 3935'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

DEC 16 1991

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	272'	-0-
				4-1/2"	3778'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Numerous casing leaks from 669'-3024'. Ran 2-3/8" tbq. to 3171'. Pumped 100 sx of 65/35 pozmix. Pulled tbq. to 2717', pumped 50 sx same cmt. & 200# hulls. Pulled tbq. to 1280', pumped 75 sx same cmt. & 350# hulls; circulated to surface. Pulled tbq. out of hole. Cemented 4 1/2" csg. w/50 sx same cmt. & 200# hulls. Pumped down 8-5/8" csg. (If additional description is necessary, use BACK of this form.) (cont.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Graham, ss.

A. Scott Ritchie III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That he has knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 125 N. Market, #1000, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 91

[Signature]
Notary Public

My Commission Expires:



with 25 sacks same cmt., p.s.i. 500#. Shut in at 500#.
Pumped 25 sacks same cmt. down 4½" csg., 300# max p.s.i.,
held. Shut in. ISIP=slight vacuum.

11/27 - Tagged cement at 241' from surface in 4½" csg.
Filled 4½" csg. with 25 sacks 50/50 pozmix cement, standing full.

