


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Graham County, Sec. 14 Twp. 10S Rge. (E) 22 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4 NE/4 SW/4  
Lease Owner FRANCIS OIL & GAS, INC. et al  
Lease Name FAULKNER Well No. 1  
Office Address 902 Palace Bldg., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 7-21 1951  
Application for plugging filed 7-21 1951  
Application for plugging approved 7-21 1951  
Plugging commenced 7-21 1951  
Plugging completed 7-21 1951  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 000 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Hays, Kansas  
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3970 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
none	---	---	---	8-5/8"	159'	none
				cemented w/140 sacks cement and 1 sack Cal. Chlor.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

Filled hole with heavy mud to within 150' of top; set plug  
cemented w/15 sacks. Filled to within 55' of top; put in  
1/2 sack hulls w/10 sacks cement to bottom of cellar.  
Pipe cut off 2' below ground.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1951  
08-01-51  
WICHITA DIVISION  
Wichita, Kans.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Francis Oil & Gas, Inc.  
Address 902 Palace Bldg., Tulsa, Okla.

STATE OF Kansas COUNTY OF Sedewick  
Robert F. Walters, partner, Fred Drilling Co. contractor and part owner  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters  
509 Orpheum Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of July, 1951  
June 28, 1952  
My commission expires

W. Marjorie Matt  
Notary Public.



22-7877-B 4-49-10M  
PLUGGING  
FILE SEC-14T10-R-220  
BOOK PAGE 97 LINE 36

FAULKNER WELL # 1

Location:	NE/4 NE/4 SW/4 Sec. 14-10S-22W Graham County, Kansas	Date Spudded:	7-8-51
Operator:	Francis Oil & Gas, Inc.	Date Rotary Compl.:	7-21-51
Contractor:	Fred Drilling Co.	Total Depth:	3970'
Surface Casing:	8 jts. 8-5/8" (163.95') set at 159' w/140 sacks cement and 1 sack Calcium Chloride.	Elevation:	2245' DF 2247' KB (2242' Gr)
Oil String:	Non run - Plugged and abandoned 7-21-51		

T O P S (KB)

Anhydrite	1746 (+ 501)
Heebner	3470 (-1223)
Lansing-Kansas City	3509 (-1262)
Base of Kansas City	3705 (-1458)
Marmaton Chert	3806 (-1559)
Conglomerate	3854 (-1607)
Simpson (Reworked)	3890 (-1643)
Arbuckle (Reworked)	3903 (-1656)
Rotary Total Depth	3970' (-1723)

L O G

(Figures indicate bottom of formation)

Shale - sand	0 to 160
Shale and sand	710
Sand and shale	1165
Shale	1350
Sand and shale	1538
Shale	1746
Anhydrite	1785
Shale	1850
Shale and shells	2325
Shale and lime	2985
Shale	3200
Shale and lime	3651
Lime	3711
Lime and shale	3806
Sandy lime and chert	3832
Lime - shale - cherty	3860
Cherty Conglomerate	3907
Lime and shale	3945
Cherty lime	3970
Rotary Total Depth	3970'

The undersigned, Fred Drilling Co., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

PLUGGING  
 FILE NO. 19-10-22W  
 BOOK PAGE 97-36

FRED DRILLING CO.

BY

*Robert F. Walters*  
Partner

Subscribed and sworn to before me this 27 day of July 1951.

*D. Marjorie Mast*  
Notary Public

My commission expires: June 28, 1952