

15-065-00614-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

Graham County. Sec. 22 Twp. 10 Rge. 10 (E) 22 (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Woodman-Iannitti Oil Co.
Lease Name Faulkner Well No. 1
Office Address 706 Un. Natl. Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 2-14-58 19__
Application for plugging filed 12-9-70 19__
Application for plugging approved 12-10-70 19__
Plugging commenced 12-26-70 19__
Plugging completed 12-26-70 19__
Reason for abandonment of well or producing formation No longer profitable.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 7-31-70 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation KC Depth to top 3600 Bottom 3836 Total Depth of Well 3932 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	138	NONE
				5 1/2	3855	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3836 feet to TOP feet for each plug set.

Plugged with pump truck	Down	5 1/2	Casing
Original plug back	3855	-	3836
1/2 Sack hulls	3836	-	3832
25 sacks cement	3832	-	280 3632
28 Sacks Jel	3632	-	280 780
50 Sacks Cement	780	-	380
3 Sacks Jel	380	-	280
40 Sacks Cement	280	-	Top 5 1/2

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1970
CONSERVATION DIVISION
Wichita, Kansas

Plugging down surface behind	5 1/2
1/2 Sack hulls	1535 - 1530
10 Sacks Jel	1530 - 280
35 Sacks cement	280 - Top Suf.


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun Oil Well Cementing
Address Box 169 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
D. J. Iannitti (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. J. Iannitti
Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of December, 19 70



My commission expires July 31, 1974
Mary M. Guenier Notary Public.

15-005-00014-0000

DRILLING LOG

Company: Woodman & Iannitti Drilling Co and Brown & Fortier

Lease: #1 Faulkner NW NW NW 22-10S-22W
Graham County, Kansas

Contractor: Woodman & Iannitti Drilling Company
P. O. Box 387, Hoisington, Kansas

Date Commenced: 2-4-58
Date Completed: 2-14-58

Total Depth: 3932

Casing: 8 5/8" at 142 with 90 sacks cement
5 1/2" at 3853 with 100 sacks cement
Figures Indicate the Bottom of Formation

0-100	Sand Post Rock	3210	Lime
139	Blue Shale	3320	Lime - Broken
350	Shale - Sand	3330	Shale - Lime
1095	Shale	3555	Lime
1370	Sand - Shale	3612	Shale - Lime
1495	Sand	3886	Lime
1840	Ribbed Shale	3932	Cong. - Chert
1845	Shale	3932	Total Depth
1888	Anhydrite		
2085	Shale - Shells		
2150	Shale - Lime		
2300	Salt Shale		
2370	Sandy Lime		
2530	Lime		
2665	Lime - Shale		

GEOLOGICAL TOPS

Elevation	2342 RB
Anhydrite	1845 /497
Heebner	3562 -1220
Toronto	3583 -1241
Lansing	3599 -1257
Marmaton Chert	3911 -1569
Total Depth	3932 -1590

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
K. T. WOODMAN