

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

API NUMBER 15-065-21,176-0000  
LEASE NAME Weigel  
WELL NUMBER 1  
4290 Ft. from S Section Line  
3739 Ft. from E Section Line  
SEC. 22 TWP. 10S RGE. 22 (E) or (W)  
COUNTY Graham  
Date Well Completed 10/27/79  
Plugging Commenced 10/22/96  
Plugging Completed 10/22/96

LEASE OPERATOR American Energies Corporation  
ADDRESS 155 N. Market, Suite 710, Wichita, KS  
PHONE# (316) 263 5785 OPERATORS LICENSE NO. 5399

Character of Well Oil (TA)  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on 9/26/96 (date)  
by Dennis Hammel (XCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing Depth to Top 3566 Bottom 3793 T.O. 3996

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
<u>Lansing</u>	<u>Oil &amp; Water</u>	<u>3566</u>	<u>3793</u>	<u>4 1/2"</u>	<u>4000</u>	<u>0</u>
				<u>8 5/8"</u>	<u>200</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Perforated @ 2150, 1839, 1050 with 2 shots per foot. The 4 1/2" casing was then filled with 260 sx of cement, 40 sx pumped down 8 5/8" casing.

Name of Plugging Contractor Allied Cementing License No. None  
Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation  
STATE OF Kansas COUNTY OF Sedgwick, ss.

Alan L. DeGood, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.  
(Signature) Alan L. DeGood  
(Address) 155 N. Market, Suite 710, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 96

Melinda S. Wooten  
Notary Public  
Melinda S. Wooten

My Commission Expires: 3-12-2000  
USE ONLY ONE SIDE OF EACH FORM

