

15-065-19212-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 22 Twp. 10 Rge. (E) 22 (W)  
Location as "NE/CNW/SW" or footage from lines C n/2 NW NW  
Lease Owner Woodman-Iannitti Oil Co.  
Lease Name Falkner Well No. 2  
Office Address 706 Un. Natl. Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 12-21-58 19  
Application for plugging filed 12-9-70 19  
Application for plugging approved 12-10-70 19  
Plugging commenced 12-26-70 19  
Plugging completed 12-26-70 19  
Reason for abandonment of well or producing formation No longer profitable

If a producing well is abandoned, date of last production & July 31 19 70  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation KC Depth to top 3568 Bottom 3693 Total Depth of Well 3800 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	139	NONE
				5 1/2	3784	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3767 feet to TOP feet for each plug set.

Plugged with pump truck Down 5 1/2 casing

Original plug back	3800	-	3777
1/2 sack hulls	3777	-	3772
25 sacks cement	3772	-	3572
28 sacks jel	3572	-	780
50 sacks cement	780	-	380
3 sacks jel	380	-	280
40 sacks cement	280	-	Top <u>5 1/2</u>

Plugging Down Surface behind 5 1/2

1/2 sack hulls	1535	-	1530
10 sacks jel	1530	-	280
35 sacks cement	280	-	Top Surface

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sun Oil Well Cementing  
Address Box 169 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
D. J. Iannitti (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. J. Iannitti  
Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 70

My commission expires July 31, 1970  
Mary M. Guessner Notary Public.



15-0065-19212-0000

DRILLING LOG

Company: Woodman & Iannitti and Brown & Fortier  
 Lease: #2 FAULKNER - C N/2 NWNW 22-10-22W  
 Graham County, Kansas  
 Contractor: Woodman & Iannitti Drilling Company  
 P. O. Box 387, Hoisington, Kansas  
 Date Commenced: 12-13-58  
 Date Completed: 12-22-58  
 Total Depth: 3800'  
 Casing: - 8 5/8" set at 139'  
 5 1/2" cemented at 3784' with 75 sacks cement &  
 100 gallons latex

Figures Indicate the Bottom of Formation

0-110	Shale & Sand	2965	Shale
300	Shale	3510	Lime & Shale
1050	Shale & Sand	3655	Lime & Shale
1320	Sand	3800	Lime
1589	Sand		
1818	Red Bed Shale & Shells		
1847	Anhydrite		
2040	Shale & Shells		
2260	Shale		
2765	Lime & Shale		

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 10 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

GEOLOGICAL TOPS

Elevation	2310 RB
Anhydrite	1818 /492
Heebner	3530 -1220
Toronto	3551 -1241
Lansing	3568 -1258
Base/Kansas City	3593 -1283
Total Depth	3800 -1490

I certify the above to be a true and correct copy of the Driller's Log and the Geological Tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: \_\_\_\_\_  
K. T. Woodman