

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,500-000

LEASE NAME Faulkner

WELL NUMBER 1-27

SPOT LOCATION SE SW SE

SEC. 27 TWP. 10S RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 11/81

Plugging Commenced 1/29/85

Plugging Completed 1/29/85

LEASE OPERATOR American Energies Corporation

ADDRESS 575 Fourth Financial Center

PHONE # (316) 263-5785 OPERATORS LICENSE NO. 5399

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DISTRICT 6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4027'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		-0-	409'	8 5/8"	404'	-0-
		-0-	2475'	4 1/2"	4037'	2475'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. BOTTOM PERFS PLUGGED W/4 SKS CMT ON BOTTOM, W/DUMP BALER, SAND TO 3840'. W/WATER FLUSH, 4 SKS CMT ON TOP. TOP PLUGGER W/30 SKS CMT, W/6 SKS HULLS, 35 SKS GEL, W/15K HULLS, 100 SKS CMT, 5 SKS GEL W/15K HULLS, 8 5/8" WIPER PLUG, 70 SKS CMT ON TOP, ALL PUMPED W/PUMP TRUCK. [CMT 60/40 POZ 8% GEL, 3% CC]

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service, Inc. License No. 960

Address 302 E. Sycamore, Box 458, Ness City, Ks. 67560

RECEIVED

STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Alan L. DeGood (employee of operator) or FEB 07 1985
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. CONSERVATION DIVISION
Wichita, Kansas

(Signature) Alan L. DeGood

(Address) 575 Fourth Financial Ctr.
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 85



Kristee Wittrig
Kristee Wittrig, Notary Public

My Commission expires: 8/31/87