

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-045-00992-0000

API NUMBER 15-OWWO

LEASE NAME Mabel

WELL NUMBER 1 (OWWO)

SPOT LOCATION NE NE SW

SEC. 22 TWP. 10 SRGE. 22 W XXXX (W)

COUNTY Graham

Date Well Completed 10/9/81

Plugging Commenced 7-8-85

Plugging Completed 7-11-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR American Energies Corporation

ADDRESS 575 Fourth Financial Center, Wichita, Ks. 67202

PHONE # (316) 263-5785 OPERATORS LICENSE NO. 5399

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? #6

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Lansing/Kansas City Depth to top \_\_\_\_\_ bottom T.D. 4023'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	218'	8 5/8"	225'	-0-
		218'	4023'	4 1/2"	3869'	1012.62

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Bottom plugged w/sand to 3680, w/4sks cement on top w/dump baler - top plugged w/ in order, 34 sks gel, 2 sks hulls, 100 sks cement, 8 5/8 wiper plug, 70 sks cement. Top plug pumped w/ pump truck. (cement 60/40 POZ 6% gel, 3% CC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service, Inc. License No. 960  
Address 302 E. Sycamore, Box 458, Ness City, Ks. 67560

STATE OF Kansas COUNTY OF Sedgwick, ss.

Alan L. DeGood (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Alan L. DeGood

(Address) 575 Fourth Financial Ctr. Wichita, Ks. 67202

AND SWORN TO before me this 14th day of July, 1985

My Commission expires: 8/31/87

CONSERVATION DIVISION  
Wichita, Kansas

KRISTEE WIDRIG  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES: 8-31-87