


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Graham County. Sec. 31 Twp. 10S Rge. 22 (W)

Location as "NE/CNW%SW%" or footage from lines NW SE SW  
Lease Owner National Cooperative Refinery Association  
Lease Name McCALL Well No. 1  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed M March 3 19 56  
Application for plugging filed March 5 19 56  
Application for plugging approved March 6 19 56  
Plugging commenced March 3 19 56  
Plugging completed March 3 19 56  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3781 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	235'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole, set Halliubton plus 15 sax of cement at 220'. Mudded hole, set Halliubton plug / 10 sax of cement. Filled on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Group Exploration Company  
Address Sterling, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C.R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) C.R. Sears (C.R. SEARS)  
305 Rule Bldg, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 19 56  
June 30, 1958  
C. ORVILLE MAY, Notary Public.



PLUGGING  
FILE SEC 31 T 10 R 22W  
BOOK PAGE 43 LINE 27

MAR 8 1956  
03-08-56  
CONSERVATION DIVISION  
Wichita, Kansas

GROUP EXPLORATION COMPANY  
Sterling, Kansas

WELL LOG-----McCALL #1

Location: NW SE SW, Section 31-10S-22W,  
Graham County, Kansas

OWNER: National Cooperative Refinery Association  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 2-22-56 (w.r.)  
COMPLETED: 3-3-56 (w.r.)

TOTAL DEPTH: 3781'

LOG

CASING RECORD

0-235	Clay, Sand & Shale
235-250	Shale
250-720	Shale & Shells
720-875	Sand
875-1525	Sand & Shale
1525-1785	Red Bed
1785-1830	Anhydrite
1830-2050	Red Bed, & Shale
2050-2225	Shale & Shells
2225-2375	Limestone & Shale
2375-2460	Limestone
2460-3470	Shale & Limestone
3470-3781	Limestone T.D.

Ran 226' of 8-5/8" casing set with  
175 sacks cement.

PRODUCTION

Plugged & Abandoned

**PLUGGING**  
FILE SEC 31 T 10 R 22W  
BOOK PAGE 43 LINE 27

STATE OF KANSAS  
DIVISION OF OIL AND GEOL  
WICHITA, KANSAS