


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County. Sec. 32 Twp. 10 Rge. 22 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
100' No. of NE SW NW
Lease Owner F & M Oil Co., Inc.
Lease Name Griffith Well No. 1
Office Address 505 Union Center, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed August 5 1977
Application for plugging filed August 5 1977
Application for plugging approved August 5 1977
Plugging commenced August 5 1977
Plugging completed August 5 1977
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3795
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 750' with 70 sacks 50/50 Pozmix, 6% Gel thru drill pipe
Mud to 200' with 20 sacks 50/50 Pozmix, 6% Gel, thru drill pipe
Mud to 40' w/ $\frac{1}{2}$ sack hulls plug and 10 sacks cement.
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

AUG 09 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.
Larry Curtis (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 8th day of August, 1977

Christy M. Hague
Notary Public.

My commission expires April 11, 1978



DRILLERS' WELL LOG

DATE COMMENCED: July 12, 1977
DATE COMPLETED: August 5, 1977

F & M Oil Co., Inc.
GRIFFITH # 1
100' No. of NE SW NW
Sec 32-T10-R22W
Graham County, Kansas

0 - 214' Rock and Clay
214 - 1135' Shale
1135 - 1792' Red Bed, Shell
1793 - 1838' Anhydrite
1838 - 3310' Shale and Lime
3310 - 3527' Lime and Shale
3527 - 3531' Shale
3531 - 3552' Lime and Shale
3552 - 3795' Lime
3795' RTD

ELEVATION: 2297 K.B.

FORMATION TOPS

Anhydrite 1793
Heebner 3527
Toronto 3552
Lansing 3567
RTD 3795

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1977
CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE:
Set used 8 5/8", 28# pipe
at 214' w/150 sacks Common,
2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 8th day of August, 1977.

Dorothy M. Hague
Notary Public



My Commission Expires: April 11, 1978