

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-01843-0000
API NUMBER Spd. 9/5/61

LEASE NAME Ganoc

WELL NUMBER 8

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3960 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 6 TWP. 10 RGE. 23 (E) or (W)

COUNTY Graham

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Date Well Completed 9/14/61

Character of Well Oil

Plugging Commenced 2:30 P.M. 5/16/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3:15 P.M. 5/16/96

The plugging proposal was approved on May 16, 1996 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3862 Bottom 3974 T.D. 4020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out.
				8 5/8	206'	None
				5 1/2	4018	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed 50 sx. down 8 5/8". Max 100%. Shut in 50%.
Mixed 250 sx. down 5 1/2". Max 600%. Shut in 100%.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. RECEIVED

Address P. O. Box 31, Russell, Kansas 67665 KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust MAY 22 1996

STATE OF KANSAS COUNTY OF Phillips, ss.


Dane G. Bales, Jr. (Employee of Operator) Wichita, Kansas of

above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 187, Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 20 day of May, 19 96



[Signature]
Betty Jane Bittel Notary Public
My Commission Expires: July 17, 1996.

15-065-01843-0000

WELL LOG

OPERATOR D. G. Hansen

SEC. 6-10-23

WELL NAME Gano #8

LOC. Approx C W $\frac{1}{2}$ W $\frac{1}{2}$ NW $\frac{1}{4}$

TOTAL DEPTH 4020'

COUNTY Graham

COMM. September 5, 1961 COMP. September 14, 1961

STATE Kansas

RIG NO. 1

ELEVATION 2457' K.B.

CASING: Ran 207' (10 jts.) 8-5/8" OD Surface Casing.
Set 5-1/2" OD Casing @4032.18' (122 jts.)

PRODUCTION: Producing

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1340	Shale & Sand		
1340	1610	Sand & Shale		
1610	1815	Sand		
1815	2072	Shale & Red Bed		
2072	2110	Anhydrite		
2110	2280	Red Bed & Shale		
2280	2540	Shell & Shale	0° - 2500	
2540	2670	Shale & Lime		
2670	2940	Lime & Shale	0° - 2750	
2940	3130	Shale & Lime	0° - 3000	
3130	3470	Lime & Shale	0° - 3250	
3470	3570	Shale & Lime	0° - 3500	
3570	3785	Lime & Shale	0° - 3750	
3785	3845	Lime		
3845	3870	Lime & Shale		DST 3818-3844'
3870	4020	Lime		DST 3858-3870'
				DST 3942-3956'
				DST 3954-3976'
				DST 3976-3996'

RECEIVED
KANSAS CORP COMM
1998 FEB 26 A 9:29

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.
By G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 18th day of September, 1961.

My commission expires:
May 20, 1963

Vicky Jacobs
Vicky Jacobs - Notary Public