

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
67202 TYPE OR PRINT

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-00603-00-01
LEASE NAME HOFF NW Wichita, KS

WELL NUMBER 301W

NOTICE: Fill out completely 2970 Ft. from (S) Section Line
and return to Cons. Div. 990 Ft. from (E) Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 6 TWP. 10S RGE. 23W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Graham
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/58
Character of Well input (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 9/10/01
FOR Plugging Completed 9/10/01

The plugging proposal was approved on 9/10/01 (date)
by Jay Pfeifer KCC Hayes, KS. (KCC District Agent's Name).
Is ACO-1 filed? no If not, is well log attached? no
Producing Formation _____ Depth to Top 3830 Bottom 3930 TD 4040' Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	195	8 5/8	195	0
		production	4038	5 1/2	4038	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Plugged well as follows : Perforated 5 1/2" at 2000' & 1200'. Pumped 325 sxs 60/40 poz, 10% gel & 500# hulls down 5 1/2" csg. Max. Press. 600#. ISIP 400#. 8 5/8" pumped 75 sx 60/40 poz, 10% gel, 300# max press., 100# ISIP. Witnessed by Jay Pfeifer w/ KCC.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK ss.
Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M Jack
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 17th day of Sept., 2001

Barbara J. Dodson
Notary Public - Barbara J. Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED
OCT 02 2001
KCC WICHITA

Handwritten initials

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566

 * INVOICE *

Invoice Number: 085336

Invoice Date: 09/18/01

Sold Murfin Drilling Co.
 To: 250 N. Water, St. #300
 Wichita, KS
 67202

USED FOR PA 36
 APPROVED J. J. RK



Cust I.D.....: Murfin
 P.O. Number...: Hoof #301
 P.O. Date.....: 09/18/01

Due Date: 10/18/01
 Terms: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	225.00	SKS	6.6500	1496.25	T
Pozmix	150.00	SKS	3.5500	532.50	T
Gel	26.00	SKS	10.0000	260.00	T
Hulls	5.00	SKS	18.0000	90.00	T
Handling	406.00	SKS	1.1000	446.60	T
Mileage (52)	52.00	MILE	16.2400	844.48	T
406 sks @\$.04 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp trk	52.00	MILE	3.0000	156.00	T

All Prices Are Net, Payable 30 Days Following Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ 430.08
 ONLY if paid within 30 days from Invoice Date

Subtotal: 4300.83
 Tax.....: 275.25
 Payments: 0.00
 Total....: 4576.08

RECEIVED
 OCT 02 2001
 KCC WICHITA

ALLIED CEMENTING CO., INC.

09910

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

R

DATE <u>9/10/01</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>9:30 A.M.</u>	JOB START	JOB FINISH <u>10:45 A.M.</u>
LEASE <u>Hoof</u>	WELL # <u>301</u>	LOCATION <u>Wakeeny N to Redline Is</u>			COUNTY <u>Chickern</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)				<u>3 1/2 w 5 FWD</u>			

CONTRACTOR	OWNER
TYPE OF JOB <u>OHF</u>	
HOLE SIZE	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT	AMOUNT ORDERED <u>375' ⁶⁰⁰ 140 10970 (600)</u>
	<u>5 Halls</u>
	<u>USED 375' ⁶⁰⁰</u>
COMMON	<u>225 @ 665 = 149625</u>
POZMIX	<u>150 @ 355 = 53250</u>
GEL	<u>26 @ 1000 = 26000</u>
CHLORIDE	<u>@</u>
<u>Halls 5'</u>	<u>@ 1800 = 9000</u>
	<u>@</u>
	<u>@</u>
	<u>@</u>
	<u>@</u>
HANDLING <u>406</u>	<u>@ 110 = 44660</u>
MILEAGE <u>44/SK</u>	<u>/ Mile = 84400</u>
RECEIVED	
OCT 02 2001	
TOTAL	<u>366900</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Paul</u>
# <u>153</u>	HELPER <u>Jason</u>
BULK TRUCK	
#	DRIVER <u>Janrod</u>
BULK TRUCK	
#	DRIVER

REMARKS:

5 1/2" Mixed 375' w/ 5 Halls
Press to 6000 psi. 400 psi. Shut in.
Annulus mixed 5000 psi. Press to 4000 psi.
Shut in @ 4000 psi.

DEPTH OF JOB	
PUMP TRUCK CHARGE <u>150</u>	<u>47500</u>
EXTRA FOOTAGE	<u>@</u>
MILEAGE <u>52</u>	<u>@ 300 = 15600</u>
PLUG	<u>@</u>
	<u>@</u>
	<u>@</u>
TOTAL	<u>63100</u>

CHARGE TO: Martin
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	<u>@</u>
	<u>@</u>
	<u>@</u>
	<u>@</u>
	<u>@</u>

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE John Lester

PRINTED NAME _____