

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM County. Sec. 7 Twp. 10 Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner DANE G HANSEN TR
Lease Name GANO C#4 Well No.
Office Address LOGAN, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MARCH 27, 1968 19
Application for plugging filed MARCH 27, 1968 19
Application for plugging approved MARCH 27, 1968 19
Plugging commenced MARCH 27, 1968 19
Plugging completed MARCH 27, 1968 19
Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

NORTH

			0

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS, MORELAND, KANSAS
Producing formation Depth to top Bottom Total Depth of Well 3970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205.55'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 1100'. SET
PLUG. PUT IN 100 SACKS CEMENT. FILLED
WITH HEAVY MUD TO 210'. SET PLUG. PUT
IN 20 SACKS CEMENT. FILLED WITH HEAVY
MUD UP TO 40'. SET PLUG. FILLED TO TOP
WITH 1/2 SACKS HULLS AND 10 SACKS CEMENT.


RECEIVED
STATE CORPORATION COMMISSION
APR 8 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G DRILLING COMPANY
Address 1107 UNION NATIONAL BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
JAY H. GALLOWAY (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) JAY H. GALLOWAY 1107 UNION NATIONAL BLDG.
(Address)

Subscribed and sworn to before me this 1st day of APRIL, 1968



Phyllis Buchanan
PHYLLIS BUCHANAN Notary Public.

W E L L L O G

OPERATOR: DANE G HANSEN TR
 WELL NAME: GANO C #4 LOCATION: NE NE NW SEC 7-10-23W
 COUNTY: GRAHAM STATE: KANSAS
 WELL COMMENCED: MARCH 20, 68 WELL COMPLETED: MARCH 27, 1968
 ELEVATION: 2412' TOTAL DEPTH: 3970'
 PRODUCTION: DRY & ABANDONED RIG NO: 1
 CASING - 8-5/8": 10 jts, 205.55' W/140 SACKS QUICKSET
 5-1/2": _____

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
205	770	SHALE	2°	1030
770	1330	SHALE & SAND	1-1/2°	1200 DST #1 3900-3922'
1330	1570	SHALE	1-1/4°	1515
1570	1781	SAND	1-1/4°	2020 DST #2 3918-3970'
1781	1935	SHALE	3/4°	2520
1935	2026	SHALE & RED BED	1-1/4°	3065
2026	2068	ANHYDRITE		
2068	2200	SHALE		
2200	2630	SHALE & SHELLS		
2630	2805	SHALE & LIME		
2805	3780	LIME & SHALE		
3780	3790	LIME		

RECEIVED
 STATE CORPORATION COMMISSION
 APR 8 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:


The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO

By

JAY H GALLOWAY

SUBSCRIBED AND SWORN TO, BEFORE ME, This 1st day of APRIL, 1968.



Phyllis Buchanan
 PHYLLIS BUCHANAN - NOTARY PUBLIC