


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 17 Twp. 10 Rge. 23W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW NE NE
Lease Owner D.G. Hansen
Lease Name Gano "C" Well No. 2
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 2 1962
Application for plugging filed December 2 1962
Application for plugging approved December 2 1962
Plugging commenced December 2 1962
Plugging completed December 2 1962
Reason for abandonment of well or producing formation Too low structually

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208.22'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550'.
Set plug. Put in 20 sacks cement.
Filled with heavy mud to 180'. Set
plug. Filled with heavy mud to 40'.
Set plug. Filled to top with 1/2
sacks hulls and 10 sacks cement.

RECEIVED

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1962

DEC 14 1962

D. G. Hansen

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G.F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G.F. Galloway
107 Rule Building
(Address)

Subscribed and sworn to before me this 6 day of December, 1962

My commission expires May 20, 1963

Vicky Jacobs
Vicky Jacobs - Notary Public.



W E L L L O G

OPERATOR D. G. Hansen SEC. 7-10-23W
 WELL NAME Gano "C" #2 LOC. SW NE NE
 TOTAL DEPTH 4005 COUNTY Graham
 COMM. 11/24/62 COMP. 12/2/62 STATE Kansas
 RIG NO. 1 ELEVATION 2413 K. B.
 CASING: Set 208.22' (10 jts.) OD Surface PRODUCTION: D & A
 Casing.

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	208	Shale-Sand		
208	1385	Shale-Sand	500' - 1/2°	
1385	1980	Red Bed-Shale	1000' - 1/2°	
1980	2023	RED Bed	1500' - 3/4°	
2023	2064	Anhydrite		
2064	2215	Shell-Shale	2075' - 1/2°	
2215	2510	Shale-Shells	2500' - 1/2°	
2510	2700	Shale-Lime		
2700	3440	Lime-Shale	3080' - 1/2°	
3440	3480	Lime	3480' - 1/4°	
3480	3670	Lime-Shale		
3670	3805	Lime		
3805	3880	Lime-Shale		
3880	3960	Lime		
3960	4005	Lime-Shale		

DST #1 3920-60

RECEIVED STATE CORPORATION COMMISSION

DEC 14 1962

RECEIVED

DEC 11 1962

CONSERVATION DIVISION Wichita, Kansas

D. G. Hansen, BY.....

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway

G. F. Galloway

THIS 6 day of December, 1962

Vicky Jacobs
Vicky Jacobs - Notary Public

