


15-065-02341-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 7 Twp. 10 Rge. 23 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Prime Drilling Company
Lease Name Gano Well No. 2
Office Address 814-16 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 28 1957
Application for plugging filed April 27 1957
Application for plugging approved April 27 1957
Plugging commenced April 27 1957
Plugging completed April 28 1957
Reason for abandonment of well or producing formation no oil in commercial quantities found.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3960 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	182'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 170'. Set Plug #1 at 170' with 15 sacks cement and 1/2 sack Hulls through drill pipe. Filled hole with extra heavy rotary mud to 40'. Set Plug #2 at 40' cemented with 10 sacks cement, 1/2 sack Hulls.

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 - 1957 05-01-57
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Prime Drilling Company
Address 814-16 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R-R. McNicol
814-16 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 1957

Darlene May
Darlene May Notary Public.

PLUGGING
FILE SEC 7 T 10 R 23w
BOOK PAGE 9 LINE 33



ROTARY DRILLING LOG

OPERATOR: Prime Drilling Company
 Gano No. 2
 NE NE SE Sec. 7-10S-23W,
 Graham County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 4/16/57
 COMP: 4/28/57

Formations:

Surface Clay	65'
Clay & Sand	135'
Shale & Shells	930'
Shale Sand Stks.	1320'
Shale & Shell	1550'
Sand	1750'
Red Bed & Shale	1995'
Anhydrite	2035'
Shale & Shell & Red Bed	2235'
Shale & Shells	2395'
Shale & Lime	3525'
Lime	3960'
Rotary Total Depth (D&A)	3960'

Remarks: Set 8-5/8" surface casing
 at 182' cemented with 160 sacks
 Pozmix, 2% C.C.

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol

RECEIVED
 STATE CORPORATION

MAY 1 1957

CONSERVATION
 DIVISION
 Wichita

PLUGGING
 FILE SEC. 7 T. 10 R. 23W
 BOOK PAGE 9 LINE 33