

1/23/10

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

CONFIDENTIAL WELL COMPLETION FORM **ORIGINAL**
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33074
 Name: Dart Cherokee Basin Operating Co., LLC
 Address: P O Box 177
 City/State/Zip: Mason MI 48854-0177
 Purchaser: Oneok
 Operator Contact Person: Beth Oswald
 Phone: (517) 244-8716
 Contractor: Name: McPherson
 License: 5675
 Wellsite Geologist: Bill Barks

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
 Operator: Dart Cherokee Basin Operating Co., LLC
 Well Name: S&F Huser B4-24 (R13E)
 Original Comp. Date: 8-31-07 Original Total Depth: 1576'
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>12-28-07</u>	<u>8-17-07</u>	<u>12-28-07</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

CONFIDENTIAL
KCC

API No. 15 - 205-27257-00-0001
 County: Wilson
 E2 SE NE Sec. 24 Twp. 30 S. R. 13 East West
 3300' FSL _____ feet from S / N (circle one) Line of Section
 460' FEL _____ feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
 (circle one) NE SE NW SW
 Lease Name: S&F Huser Well #: B4-24 (R13E)
 Field Name: Cherokee Basin Coal Gas Area
 Producing Formation: Penn Coals
 Elevation: Ground: 944' Kelly Bushing: _____
 Total Depth: 1576' Plug Back Total Depth: 1569'
 Amount of Surface Pipe Set and Cemented at 40 Feet
 Multiple Stage Cementing Collar Used? Yes No
 If yes, show depth set _____ Feet
 If Alternate II completion, cement circulated from _____
 feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan RENS 331-07
 (Data must be collected from the Reserve Pit)
 Chloride content _____ ppm Fluid volume _____ bbls
 Dewatering method used _____
 Location of fluid disposal if hauled offsite: _____
 Operator Name: _____
 Lease Name: _____ License No.: _____
 Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
 County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
 Title: Eng. Clerk Date: 1-23-08
 Subscribed and sworn to before me this 23rd day of January
 Notary Public: Amanda L. Eifert
 AMANDA L. EIFERT
 NOTARY PUBLIC, STATE OF KANSAS
 COUNTY OF LIVINGSTON
 MY COMMISSION EXPIRES ON 7, 2012
 ACTING IN COUNTY OF Ingham
 Date Commission Expires: 10/7/2012

KCC Office Use ONLY

Letter of Confidentiality Attached
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
 KANSAS CORPORATION COMMISSION
JAN 28 2008

CONSERVATION DIVISION
WICHITA, KS

Operator Name: Dart Cherokee Basin Operating Co., LLC Lease Name: S&F Huser Well #: B4-24 (R13E)
 Sec. 24 Twp. 30 S. R. 13 East West County: Wilson

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: High Resolution Compensated Density Neutron & Dual Induction	Log Formation (Top), Depth and Datum <input checked="" type="checkbox"/> Sample Name Top Datum <div style="text-align: center; font-weight: bold; font-size: 1.2em;"> CONFIDENTIAL JAN 23 2008 KCC </div>
--	---

CASING RECORD							
				New	Used		
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surf	11"	8 5/8"	24#	40'	Class A	8	
Prod	6 3/4"	4 1/2"	9.5#	1570'	Thick Set	160	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
4	1284.5' - 1286'	100 gal 15% HCl, 2310# sd, 80 BBL fl	
6	1181.5' - 1182.5'	150 gal 15% HCl, 2025# sd, 100 BBL fl	
6	1046.5' - 1047.5'	100 gal 15% HCl, 2020# sd, 90 BBL fl	
6	843.5' - 844.5' / 822.5' - 823.5'	100 gal 15% HCl, 4035# sd, 8 ball sealers, 190 BBL fl	
6	739' - 740.5'	100 gal 15% HCl, 3020# sd, 140 BBL fl	

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2 3/8"	1325'	NA	Yes <input checked="" type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr.	Producing Method
12-30-07	Flowing <input type="checkbox"/> Pumping <input checked="" type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) <input type="checkbox"/>

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	NA	14	77	NA	NA

Disposition of Gas Vented Sold Used on Lease *(If vented, Sumit ACO-18.)*

Method of Completion: Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

RECEIVED
 KANSAS CORPORATION COMMISSION

JAN 28 2008

CONSERVATION DIVISION
 WICHITA, KS