

15-065-01727-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Drilling Completed  
September, 1954

API NUMBER \_\_\_\_\_  
LEASE NAME DeYoung "A"

WELL NUMBER #4

4290 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 10S RGE. 21 (W)

COUNTY Graham

Date Well Completed 9-20-54

12:30 P.M.

Plugging Commenced 5-17-88

1:45 P.M.

Plugging Completed 5-17-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352, Russell, KS 67665

PHONE# (913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 12, 1988 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3838' Bottom 3841' T.D. 3841'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pull
Arbuckle	Oil	3838'	41'	8-5/8"	159'	159'
				5-1/2"	3839'	

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Down the 5-1/2" casing @ 400# maximum pressure. Mixed 25 sks. cement -  
then mixed 4 sks. hulls w/150 sks. cement and shut in @ 150#.  
Down annulus (8-5/8" casing) @ 200# maximum pressure. Mixed 75 sks.  
cement and shut in @ 100#. The casing was perforated 3 shots @ 950' prior to  
(if additional description is necessary, use BACK of this form.) cementing.

Name of Plugging Contractor John O. Farmer, Inc. License No. 5135

Address P.O. Box 352, Russell, KS 67665


STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1988



Margaret A. Schulte  
Notary Public

Margaret A. Schulte

