

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-065-01876-0000

API NUMBER Unknown

LEASE NAME Diebolt LKC Unit

WELL NUMBER 2-1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 16 TWP. 10 RGE. 23 or (W)

COUNTY Graham

Date Well Completed 03/08/55

Plugging Commenced 10/15/91

Plugging Completed 10/15/91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Geneva Resources, Inc.

50 California Street, Suite 930

ADDRESS San Francisco, CA 94111

PHONE#(415) 291-9500 OPERATORS LICENSE NO. 30241

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 15, 1991 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, Is well log attached? Yes

Producing Formation LKC Depth to Top 3647' Bottom 3874' T.D. 4041'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	278'	8-5/8"	278'	None
LKC	Oil	Surface	4023'	5-1/2"	4023'	None

STATE CORPORATION COMMISSION

NOV 4 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated at 1100' and 1925'. Pumped down 5-1/2" csg with 250 sx 65/35 pozmix containing 10% gel and 400 lbs of hulls to a maximum 500 psi and shut in at 300 psi. Pumped down 8-5/8" surface casing with 100 sx of 65/35 pozmix containing 10% gel and 100 lbs of hulls to a maximum pressure of 300 psi and closed in at 150 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. \_\_\_\_\_

Address P. O. Box 31, Russell, KS 67655


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.

STATE OF California COUNTY OF San Francisco, ss.

Thomas G. Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas G. Smith

(Address) 50 California Street, Suite 930 San Francisco, CA 94111



AND SWORN TO before me this 31st day of October, 19 91

Jacquelyn Wishom  
 Notary Public

My Commission Expires June 16, 1995