

15-065-01880-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER UnknownLEASE NAME Diebolt LKC UnitWELL NUMBER 2-5

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from S Section Line3630 Ft. from E Section LineSEC. 16 TWP. 10 RGE. 23 ~~06~~ or (W)LEASE OPERATOR Geneva Resources, Inc.  
ADDRESS 50 California St., Ste. 930, San Francisco, CA 94111COUNTY GrahamPHONE# (415) 291-9500 OPERATORS LICENSE NO. 30241

Date Well Completed \_\_\_\_\_

Character of Well OilPlugging Commenced 07/19/91

(Oil, Gas, D&amp;A, SWD, Input, Water Supply Well)

Plugging Completed 07/19/91The plugging proposal was approved on 07/19/91 (date)by Carl Goodrow (KCC District Agent's Name).Is ACO-1 filed? Unknown If not, is well log attached? No - Not AvailableProducing Formation LKC Depth to Top 3689' Bottom 3788' T.D. 3791'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

| Formation | Content | From    | To   | Size   | Put In | Pulled out |
|-----------|---------|---------|------|--------|--------|------------|
|           |         | Surface | 278  | 8-5/8" | 278'   | None       |
| LKC       | Oil     | Surface | 3869 | 5-1/2" | 3869'  | None       |
|           |         |         |      |        |        |            |
|           |         |         |      |        |        |            |

SEP 03 1991

WICHITA DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran tbg in hole and circ 150 sx cmt blend out 5-1/2" and 8-5/8" casing. Closed in 8-5/8" casing and POOH with tubing. Squeezed 5-1/2" and 8-5/8" casings with 200 sx cmt blend. Pumped cmt at a max press of 800 psi and closed in at a pressure of 500 psi. Cement blend consisted of 350 sx of 65/35 pozmix containing 10% gel and 500 lbs hulls.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Express Well Service License No. 6426Address P. O. Box 426, Victoria, KS 67671NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.STATE OF California COUNTY OF San Francisco, ss.

Thomas G. Smith

(Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas G. Smith

50 California Street, Suite 930

(Address) San Francisco, CA 94111

OFFICIAL NOTARY SEAL  
JULIA A. SCHNEIDER  
Notary Public - California  
SAN FRANCISCO COUNTY  
My Comm Expires MAR 28, 1995

SUBSCRIBED AND SWORN TO before me this 29TH day of August, 19 91

Julia A. Schneider  
Notary Public

My Commission Expires: March 28, 1995