

15-065-01877-000Z

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Diebolt LKC UnitWELL NUMBER 2-2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line4950 Ft. from E Section LineLEASE OPERATOR Geneva Resources, Inc.SEC. 16 TWP. 10 RGE. 23 ~~XX~~ or (W)ADDRESS 50 California Street, Suite 930, San Francisco, CA 94111 COUNTY GrahamPHONE# (415) 291-9500 OPERATORS LICENSE NO. 30241Date Well Completed 4/22/55Character of Well OilPlugging Commenced 5/14/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5/14/90The plugging proposal was approved on 5/14/90 (date)by Don Butcher/Dale Balthazor/Carl Goodrow (KCC District Agent's Name).Is ACO-1 filed? Unknown If not, Is well log attached? YesProducing Formation LKC Depth to Top 3630' Bottom 3870' T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	278'	8-5/8"	278'	None
<u>LKC</u>	<u>Oil</u>	<u>Surface</u>	<u>3899</u>	<u>5 1/2"</u>	<u>3889'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated @ 1100' and 1925'. Ran tubing to 2198'. Circulated cement to surface with 19 sx. Squeezed 5 1/2" casing with 220 sx 65/35 poz with 6% gel and 500 lbs. hulls. Squeezed 8-5/8" casing with 30 sacks.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287Address P. O. Box 428, Hays, KS 67601NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.STATE OF California COUNTY OF San Francisco, ss.Thomas G. Smith

(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Thomas G. Smith(Address) 50 California St., Ste 930, San Francisco, CA 94111

OFFICIAL SEAL
JACQUELYN WISHOM
NOTARY PUBLIC - CALIFORNIA
SAN FRANCISCO COUNTY
My comm. expires FEB 8, 1991

AND SWORN TO before me this 20th day of June, 19 9006-2590

CONSERVATION DIVISION
Wichita, Kansas

Expires: 2-8-91

Notary Public