

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,164-00-00

LEASE NAME Hacker "A" #3

WELL NUMBER _____

SPOT LOCATION NE NE NE

SEC. 10 TWP. 12s RGE. 22w(E) or (W)

COUNTY Trego

Date Well Completed _____

Plugging Commenced 12/6/85

Plugging Completed 12/26/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. Scott Ritchie

ADDRESS 125 N. Market, Suite 950, Wichita, Ks. 67202

PHONE # (316) 267-4375 OPERATORS LICENSE NO. 5198

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4051'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	207'	none
				4 1/2"	4064'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plug job - No pipe recovery. Plugged bottom with sand to 3641' & 4 sacks cement.

Shot pipe at 3000', 2614', & 2221'. Hole was squeezed. Plugged well down 4 1/2" with 50 sacks cement, 2 hulls, 15 gel, & 50 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1985

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION
Notary Public

JAN 3 1986
01-03-1986
CONSERVATION DIVISION

Form CP-4
Revised 01-84