

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21252-0000

LEASE NAME Grecian

WELL NUMBER 1

SPOT LOCATION NE NW

SEC. 10 TWP. 12 RGE. 22 (E) or (W)

COUNTY Frego

Date Well Completed 8/4/83

Plugging Commenced 10/10/86

Plugging Completed 10/10/86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D R Well Operators, Inc.

ADDRESS 7585 W. Arkansas, Suite B

Lakewood, CO 80226

PHONE # (303) 988-1780 OPERATORS LICENSE NO. 9856

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Marmaton Depth to top 3998 bottom 4014 T.D. 4110

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Dry	3416	3620	4 1/2" 10.	5# 4060.	03' None
Toronto	Water	3651	3662			
L/KC	Show water&oil	3666	3918	8 5/8	2121	None
Marmaton	oil	3996	4032			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. We tied into the backside and pumped 60 sacks down backside. Max. pressure of 300#. Hooked up to production casing and plugged with 60 sacks cement, 4 sacks hulls and 130 sacks of thrifty-mix cement. Max. pressure was 1200#. Shut in pressure was 900#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Services Co. License No. _____

Address Box 69, Hays, Kansas 67601

STATE OF Colorado COUNTY OF Jefferson, ss.

Daniel R. Sommer (employee of operator) or 11-06-1986
(operator) of above-described well, being first duly sworn on oath, says: NOV 6 1986
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Daniel R. Sommer

(Address) 7585 W. Arkansas, Ste. B
Lakewood, CO 80226

SUBSCRIBED AND SWORN TO before me this 4th day of NOVEMBER, 1986

Patrick N. Swenson
Notary Public



Expires: March 17, 1990