

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-065-03075-0000

API NUMBER \_\_\_\_\_

LEASE NAME Diebolt LKC Unit

WELL NUMBER 1-3

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 17 TWP. 10 RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 3/31/55

Plugging Commenced 10/17/90

Plugging Completed 10/17/90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Geneva Resources, Inc.

ADDRESS 50 California St, Ste 930, San Francisco, CA

PHONE# (415) 291-9500 OPERATORS LICENSE NO. 30241 <sup>94111</sup>

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 17, 1990 (date)

by Carl Goodrow/Don Butcher (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3644' Bottom 3852' T.D. 3890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surf.	282	8-5/8"	282'	None
LKC	Oil	Surf.	3883	5-1/2"	3883'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set. Perforated the Base of the Dakota at 1100' and the Base of the Anhydrite at 1925'. Ran tbg to 2000' and pumped 100 sx cement. Pulled tbg to 1000' and pumped 45 sx. Circulated. Pulled tbg. Squeezed 5-1/2" csg with 55 sx cement. Max pressure 425 psi. Closed in at 300 psi. Pumped down 8-5/8" surface csg with 100 sx to a max pressure of 200 psi. Closed in at 175 psi.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P. O. Box 428, Hays, KS 67672

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geneva Resources, Inc.


STATE OF California COUNTY OF San Francisco, ss.

Thomas G. Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION (Signature) Thomas G. Smith  
 50 California Street, Suite 930  
 San Francisco, CA 94111

SUBSCRIBED AND SWORN TO before me this 2<sup>ND</sup> day of November, 19 90

CONSERVATION DIVISION (Notary Public) Jacquelyn Wishom  
 Wichita, Kansas



Expires: 2-8-91