

15-065-20110-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 17 Twp. 10 Rge. 23 (E) (W) x
Location as "NE/CNW/SW" or footage from lines 2640' from N. line; 2310' from W.
Lease Owner Petroleum Management Inc. line
Lease Name Deitz Well No. #1
Office Address Box 922, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 7-28-69 _____ 19____
Plugging completed _____ 7-30-69 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well W. L. Nichols BTKCC
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3922' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3939'	2620.97'
				8 5/8"	208'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3725'. Mixed and dumped 3 sacks cement thru dump bailer.
Squeeze hole with 5 sacks hulls, 15 sacks gel, 100 sacks cement from 1025' to 700'.
12 sacks gel from 700' to 220' - 20 sacks cement from 220' to 160' - 3 sacks gel from 160 to 40' - 10 sacks cement from 40' to 0'.

STATE RECEIVED
CORPORATION COMMISSION
AUG 5 1969
CONSERVATION DIVISION
Wichita, Kansas
08-05-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 4 day of August, 19 69

My commission expires October 1972
SIDNEY MILLER
NOTARY PUBLIC
BARTON COUNTY, KANSAS

Sidney Miller
Notary Public.

15-065-20110-0000

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1969
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Dietz No. 1

CASING RECORD:	COMPANY: Petroleum Management, Inc.	DESCRIPTION:
3 5/8" @ 208.70 w/180 sx cement	CONTRACTOR: Red Tiger Drilling Co.	2640' FNL & 2310' FWL of
4 1/2" @ 3939.1 w/250 sx cement	COMMENCED: December 6, 1967	17-10S-23W Graham Co., Ks.
TOTAL DEPTH: 3940'	COMPLETED: December 14, 1967	ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Shells	0	209	
Shale	209	1100	
Shale & Sand	1100	1310	
Shale & Shells	1310	1495	
Sand & Shale	1495	1710	
Shale & Shells	1710	1968	
Anhydrite	1968	2008	
Shale & Shells	2008	2480	
Lime & Shale	2480	3700	
Lime	3700	3940	


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 18th day of December, 1967.

Betty M. Maloney
Notary Public



My Commission Expires: 12-31-71