

15-065-02298-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 17 Twp. 10S Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Peel-Hardman Oil Operators NE RTCC
Lease Name Stewart Well No. 1
Office Address R.R. #3, Box 144B, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 27, 1957
Application for plugging filed Jan. 27, 1957
Application for plugging approved Jan. 27, 1957
Plugging commenced Jan. 27, 1957
Plugging completed Jan. 27, 1957
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	240'	8 5/8"	240	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3900' to 230' - heavy rotary mud and wooden plug
230' to 168' - 1/2 sack hulls and 20 sacks cement
168' to 40' - heavy rotary mud and wooden plug
40' to 6' - 1/2 sack hulls and 10 sacks cement
6' to surface- cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY: Al H. Smith
P.O. Box 88, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1957

My commission expires April 27, 1960

RECEIVED
STATE CORPORATION COMMISSION

Notary Public.

PLUGGING
FILE SEC 17 T 10 R 22W
BOOK PAGE 132 LI 34

FEB - 7 1957
CONSERVATION DIVISION
Wichita, Kansas

15-065-02298-0000

DRILLERS' LOG RTKCC

Company: Peel-Hardman Oil Operators
Farm Name: Stewart Well No. 1
Total Depth: 3900'
Comm: 1/18/57 Comp: 1/27/57
Contractor: Peel Brothers, Inc.
Casing: 8 5/8" @ 240' cem.

NE
SE SE NE
Sec. 17, Twp. 10S, Rge. 23W,
County: Graham,
Kansas
Elevation:
Production: Dry

Figures below indicate bottoms of formations:

Surface soils	0 -	240
Shale		750
Sand and shale		850
Shale		950
Sand		1000
Shale		1680
Red bed and shale		1905
Anhydrite		1945
Red rock and shale		2320
Lime and shale		2665
Lime		2800
Lime and shale		3345
Lime		3418
Lime and shale		3485
Lime		3835
Lime and shale		3850
Lime, shale and chert		3900
Total Depth		3900

This is to certify that the above information is to the best of our knowledge, true and correct.


PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 28th day of January, 1957

My commission expires: April 27, 1960

Ruth Blank
Notary Public



RECEIVED
STATE CORPORATE COMMISSION

FEB - 7 1957

CONSERVATION DIVISION
Topeka, Kansas

PLUGGING
WELL NO. 17 T. 10. R. 23W.
BOOK PAGE 132 L.F. 34