

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 26 Twp. 10S Rge. 21W
Location as "NE/CNW, SW1" or footage from lines
NE/4 1650' WEL & 165' SNL


Lease Owner Icer Addis
Lease Name Barber Well No. 4
Office Address 5307 E. Central, Wichita, KS 67208
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed April 20 1979
Application for plugging filed April 20 1979
Application for plugging approved April 20 1979
Plugging commenced April 20 1979
Plugging completed April 20 1979
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor, Palco, KS
Producing formation Depth to top Bottom Total Depth of Well 3785
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole w/rotary mud, pumped 70 sx 50/50 pozmix w/6% gel, thru open end
D.P. @ 800'; mud to 200'; pumped 20 sx thru open end D.P., mud to 40';
1/2 sx hulls & wood plug for solid bridge, pumped 10 sx to base of cellar
5 sx in rathole, completed at 12:15 p.m. 4-20-79 by Sun.

Witnessed: Gilbert Balthazor St. Plugger, Palco, Kansas
Gary Bagby, Sterling, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1979
4-24-1979

(If additional description is necessary, use BACK OF THIS SECTION)
Name of Plugging Contractor HUSKY DRILLING CO., INC. Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) HUSKY DRILLING CO., INC.
800 Bittling Building, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1979

Geraldine Stewart
Geraldine Stewart Notary Public.

My commission expires January 12, 1981





800 Bitting Bldg
Wichita, Kansas 67202
Phone 316 - 263-7904
Mobile Phone 316 - 793-7859 Unit 7070

April 20, 1979

WELL LOG-----Barber No. 4
Location: NE/4- 1650' of Sec. 26-10S-21W, Graham County, Kansas
WEL & 165'SNL

OWNER: Icer Addis
ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: April 14, 1979
COMPLETED: April 20, 1979

Rotary Total Depth: 3785'

LOG

0 - 215 Soil, sand & shale
215 - 450 Shale
450 - 1636 Shale & sand
1636 - 1687 Anhydrite
1687 - 1970 Shale & shells
1970 - 3362 Shale & lime
3362 - 3478 Lime
3478 - 3565 Lime & Shale
3565 - 3718 Lime
3718 - 3761 Lime & Shale
3761 - 3771 Lime
3771 - 3785 Dolomite

CASING RECORD

Ran 5 jts., 8-5/8, 20#, 8V, Rge 3, used
csg., tallied @ 206', set @ 215 K.B.
w/150 sx 60/40 pozmix, 2% gel, 3% cc -
circulated; plug down @ 8:45 p.m. by
Sun 4-14-79.

Plugged 4-20-79.

RECEIVED
STATE CORPORATION COMMISSION
4-24-1979
APR 24 1979
CONSERVATION DIVISION
Wichita, Kansas