


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM County. Sec. 26 Twp. 10S Rge. 21W ~~XXX~~ (W)

Location as "NE/CNW%SW%" or footage from lines SW SW NW
Lease Owner SIERRA PETROLEUM CO., INC.
Lease Name HOLZHAUER Well No. 1
Office Address 211 North Broadway, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed August 5, 19 53
Application for plugging filed December 19, 19 66
Application for plugging approved December 20, 19 66
Plugging commenced December 30, 19 66
Plugging completed December 30, 19 66
Reason for abandonment of well or producing formation Non-#economic

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production September 15, 19 64
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas 67650
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3707 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	-0-	190'	8-5/8"	190'	None
	Oil String	-0-	3705'	5-1/2"	3705'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

12-30-66 Pumped 7 sx. gel & 5 sx. cement down 8-5/8" casing. Shut-in pressure 100 psi.

Pumped 35 sx. gel & 3sx. hulls down 5 1/2" casing. Pumped in 80 sx. cement. Pumping pressure 500 psi. Shut-in at 200 psi. All the while cement was being pumped in 5 1/2" casing, pressure on 8-5/8" casing stayed constant.

RECEIVED
STATE CORPORATION COMMISSION
1-9-1967
JAN 9 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 211 North Broadway, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
G. A. Hall (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. A. Hall, Prod. Supt.

Sierra Petroleum Co., Box 232
(Address) Russell, Kansas 67665

SUBSCRIBED AND SWORN to before me this 6th day of January, 19 67

10-17-67

Notary Public.



Trans Era Petroleum, Inc.
Holtzler #1

S# SW NW 28-10-21
Graham County, Ke.

Total Depth: 3707'
Comm. 7/20/53
Comp. 8/5/53

Casing

8 5/8" Set @ 100'
5 1/2" Set @ 3705'

Cement

140 sacks of Victor
100 sacks of Lone Star

RECEIVED
STATE CORPORATION COMMISSION
12-20-1966
DEC 20 1966

CONSERVATION DIVISION
Wichita, Kansas

Formation

Depth

Sand	55
Shale-sand streaks	100
Shale-sand	160
Shale-shells	720
Sand	754
Hard sand	760
Sand	800
Sand-shale	840
Shale-shells	1120
Sand-Dakota	1285
Shale-red bed	1270
Sand	1290
Shale-red bed	1390
Shale-shells	2200
Lime-shale	2345
Broken lime	2375
Lime	2550
Lime-sand streaks	2650
Lime	2760
Shale-lime	3440
Lime	3622
Shale-lime	3707'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to
the best of my knowledge.

G. A. Hall
(for) G. A. Hall, Prod. Supt.

Subscribed and sworn to before me this 12th day of August, 1953.

Henry Hall
Notary Public

My commission expires: 1-30-57.

