


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 75-6

LOCATION SE-NE-NE

SEC. 1 TWP. 21 RGE. 12W

Dry Hole        Abandoned Oil Well X Abandoned Gas Well       

I have today completed supervision of plugging of:

Well No. 2 Lease Frank Cook

Operator Imperial Pecos Co, Inc. Address 203 N. N. Bk. Bldg. Wichita-Kans.

Field        County Stafford

Total Depth 3464 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 291 ft. Circulated with cement.  
5/8" casing set at 3413 ft. - 125 sacks of cement - Trenchless Plug  
at 3300 ft. filled hole with chat from 3300 ft. to 3275 ft. - Dumped  
15 sacks cement at 3275 ft. - Shut off & pulled the 5/8" casing  
and to 290 ft. - Set Rock Bridge & 15 sacks of cement at 290 ft.  
Mud to 35 ft. - Bridge x 10 sacks of cement  
at the surface.

Miller Casing Pulling Co. Plugging Contractors

**PLUGGING**  
FILE SEC. L T 21 R 12W  
BOOK PAGE 75 LINE 6

STATE CORP. COMMISSION  
SEP 14 1951  
CONSERVATION DIVISION  
Wichita, Kansas  
C. M. Stouch  
District Conservation Agent

Date 9-11-51