

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 72-25

LOCATION NW NE NW

SEC. 9 TWP. 10 RGE. 21

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4 Lease Martin

Operator Skelly Oil Co Address Box 391 Hutchinson, Kans

Field _____ County Graham

Total Depth 3890 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 279' circulated with cement - 5 1/2" at 3890' with
200 sax cement behind - P.B. to 3570', perforated at 3551',
Filled with sand to 3540', set 4 sax cement with dump bailer,
pulled 3065' 5 1/2" - heavy mud to 270', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
7-7-1956
JUL 7 - 1956

District Conservation Agent
7-3-56

Date _____

PLUGGING
FILE SEC. 9 T. 10 R. 21 W
BOOK PAGE 72 LINE 25

CONSERVATION DIVISION
Wichita, Kansas